

2

Re-Record - No Charge 12/1

JACKSON COUNTY APPROVED LAND CORNER P.A. 345 of 1990

ACTING Chairman Dean R. Gutekunst Date 12-20-1995

SOUTH 1/4 POST, SECTION 34 COLUMBIA TOWNSHIP

SUPERCEEDS Liber 1482, Page 618

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1501 PAGE 1111

For corners in JACKSON (County)

Located In: Corner Code #

- 1. Public Land Survey T 4 S R 1 E H-13
2. Property Controlling in Section S T R REMONUMENTATION
3. Miscellaneous Property in Sec. S T R FEB 2 2 1996
4. Lot No. Recorded Plat
5. Private Claims

STATE OF MICHIGAN JACKSON COUNTY RECORDED 29 DEC 95 11:17 A.M. Register of Deeds Stamp & File Number GERALD J. McDEVITT REGISTER OF DEEDS

COMMISSION

DEAN R. GUTEKUNST in a field survey on November 10, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. Contains numbers 1-36 and a circled 14.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Original Government Post set by Benjamin Hough, Deputy Surveyor, 1815 W. Oak 30" N 83 1/2 E 57 links (37.62') W. Oak 20" N 11 E 54 links (35.64') Perpetuation by M. S. Cook, date unknown W. Oak 24" S 68 W 193 1/2 links (127.71') Continued on back,



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found dark blue STONE, 1.5' below gravel surface, with a flat (1/4" x 1 1/2") bar 0.3' North of center line of stone. Top of stone is flat and about 4" East & West, and 3" North & South. Also found a red stone, 2.0' below blacktop surface, with a lightning rod at the Southeast corner of the stone, for the North 1/4 Post of Section 3, T5S, R1E, Woodstock Township, Lenawee County. This stone is rounded and about 8" x 8" X 10". Set a 3/8" rod on top of stone, to surface. Corner is 1 1/2' South of center line of blacktop running West, 2' West of center line of blacktop road running North and 21' East of a fence South. Continued on back,

\$ 2.00 REMONUMENTATION \$ 9.00 CORNER REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: H-13 T4S, R1E Corner is a 4" diameter X 36" concrete monument with a 1/2" X 36" steel rod and an aluminum cap stamped LS 18658, which is the standard monument for Jackson County. S 10° E 30" Evergreen 81.43' 40d & washer on West side S 5° E Northwest corner of foundation of House #15776 175.80' N 45° E Utility Pole 69.16' 40d & washer on Southeast side S 45° W Southeast corner of steel Consumers Power Co. Tower 145.55' (Top of base of leg of tower - 1' above ground) Southerly Steel post with survey marker sign attached 24.2' Westerly North 1/4 Post of Section 3, T5S, R1E, Woodstock Township, Lenawee County 23.41' N 30° W Found 1 1/2" solid iron 6.35'

Signed by Dean R. Gutekunst Date December 12, 1995 Surveyor's Michigan License No. 18658