

Chairman Dean [Signature]  
 Date Dec. 20, 1994

REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1451 PAGE 419

For corners in

JACKSON (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45</u> R <u>1W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
 JACKSON COUNTY  
 REGISTERED

30 DEC 94 3:29 P.M.

GERALD J. McDEVITT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, John E. Maxson in a field survey on 4 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST SET IN ORIGINAL GOVERNMENT SURVEY BY JOSEPH WAMPLER 1923  
 40"W.Oak, N69.5W, 41.5 lks (27.39 ft) - 32"W.Oak, N13E, 39.5 lks (26.07 ft)  
 Corner to South, 190 lks (125.40 ft) East  
 TIMOTHY B. VANGIESON, RLS#24621 SURVEY IN LIBER 558, PAGE 848, HILLSDALE  
 COUNTY CALLS FOR 3/4" CRIMP PIPE 124.05 FEET EAST OF 1/2" PIPE AT E-1, T5S-R1W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE, DUG TO A DEPTH OF 3 FEET AND FOUND NOTHING. THIS PIPE FITS PROPORTIONATE DISTANCES EAST AND WEST AND THE FALLING TO E-1, T5S-R1W. ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 REPLACED WITH STANDARD 4" CONCRETE MONUMENT AND CAP

SURVEY &  
 REMONUMENTATION


MAY 08 1995

COMMISSION

\$ 2.00 REMONUMENTATION  
 \$ 7.00 CORNER REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 4" DIAMETER CONCRETE MONUMENT WITH JACKSON COUNTY REMONUMENTATION  
 CAP STAMPED LS#27454  
 S25E 31.31' NAIL IN 26" MAPLE  
 S24W 33.68' NAIL IN 12" SASSAFRAS  
 N32W 64.57' NAIL IN 34" OAK  
 N63W 73.76' NAIL IN 46" OAK  
 EAST 124.05' CAPPED 5/8" IRON AT E-1, T5S-R1W



Signed by John E. Maxson  
 Surveyor's Michigan License No. \_\_\_\_\_

Date 8 December