

**JACKSON COUNTY**  
**APPROVED LAND CORNER** SE CORNER SECTION 33, LIBERTY TOWNSHIP  
**P.A. 343 of 1990**

Chairman Dean R. Suber  
 Date Dec. 20, 1994

REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **1451** PAGE **421**

For corners in

JACKSON (County)	Located In:	Corner Code #
1. Public Land Survey	T 4S R 1W	G-13,
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN  
 JACKSON COUNTY  
 RECORDED

30 DEC 94 3:30 P.M.

GERALD J. McDEVITT  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John E. Maxson in a field survey on 4 November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

POST SET IN ORIGINAL GOVERNMENT SURVEY BY JOSEPH WAMPLER 1823  
 11"W.Oak, N43W, 11.5 lks ( 7.59 ft) - 8"W.Oak, N23E, 22 lks (14.52 ft)  
 Corner to South, 262 lks (172.92 ft) East

1885 HILLSDALE COUNTY RECORD REPORTS THE NORTHWEST CORNER OF SECTION 3 BEING  
 262 LINKS EAST OF A STONE AT THE SOUTHWEST CORNER OF SECTION 34

TIMOTHY B. VANGIESCH, RLS#24621 RECORDED CORNER IN OCTOBER 1978 (LIBER 3,  
 PAGE 149) AS 3/4" PINCHED PIPE  
 15" Walnut, N30E, 103.34' - Power pole, S75E, 83.47' - 10"Oak, S20W, 39.30'  
 36"Oak, N30W, 45.23'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PINCHED PIPE AS RECORDED OVER STONE AND BRICK AND ACCEPTED AS A  
 CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 REPLACED WITH STANDARD 4" CONCRETE MONUMENT AND CAP

**SURVEY &  
 REMONUMENTATION**

MAY 08 1995

COMMISSION

\$ 2.00 REMONUMENTATION  
 \$ 7.00 CORNER REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 4" DIAMETER CONCRETE MONUMENT WITH JACKSON COUNTY REMONUMENTATION  
 CAP STAMPED LS#27454  
 N72E 102.50' NAIL IN 30"WALNUT  
 N25W 44.62' NAIL IN 42"OAK  
 S22W 38.90' NAIL IN 40"OBL.OAK  
 S65W 97.80' NAIL IN POWER POLE  
 EAST 178.05' CAPPED 5/8 IRON AT G-1, T5S-R1W



Signed by John E. Maxson Date 3 December 1994  
 Surveyor's Michigan License No. \_\_\_\_\_