

**JACKSON COUNTY  
APPROVED LAND CORNER  
P.A. 343 of 1990**

**SOUTH 1/4 POST SECTION 26  
NORTH 1/4 POST SECTION 35  
LIBERTY TOWNSHIP**

Chairman Dean R. [Signature]  
Date Dec. 21, 1998

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in <u>Jackson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4</u> S. R1 <u>W.</u>	<u>J-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____



Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Timothy B. VanGieson, in a field survey on April 08, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

- J-11: Original government survey by Hervey Parke D.S. on or about February 19, 1825.  
"Wood Stake"  
White Oak 32" N 54° E 0.11 ch. (7.26')  
Yellow Oak 24" S 75° W 0.12 ch. (7.92')  
"39.92 ch. set 1/4 section post on true line."
- J-11: P.T. Cook on or about April 22, 1880  
"Found original stake by stumps to both witnesses."  
Hickory 16" N 48° W 55 lks. (34.16')  
White Oak 30" S 20°-10" E 62-3/4 lks. (41.42')  
"Set stone with "+" on top."
- J-11: No P.A. 74 recordings.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- J-11: None of the above accessories remain standing. Found depression where P.T. Cook's hickory may have stood.  
Found 20" x 13" x 6" blue granite stone with "+" on top, flush with the existing ground surface, at the East side of an old wood anchor post.

Accepted stone as faithful and careful perpetuation of corner set on or about February 19, 1825.

Replaced stone with standard Jackson County Remonumentation monument and left stone on South side of said monument.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- J-11: 4" x 36" concrete Jackson County Remonumentation monument with aluminum cap: R.L.S. No. 24621  
N 00° E Remonumentation corner sign 00.50'  
N 23° E 60-d in West side 17" Red Oak 62.29'  
S 83° E 60-d in South side 12" Cherry 13.27'  
S 13° E 60-d in East side 17" White Oak 60.55'  
N 48° W 60-d in North side 15" White Oak 58.07'  
N 10° W 60-d in West side 9" Hickory 48.30'  
All bearings are magnetic  
All distances E.D.M. measured



Signed by Timothy B. VanGieson  
Surveyor's Michigan License No. 24621

Date December 19, 1998