

Chairman Donald Sattam
 Date Dec. 20, 1994

REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ JACKSON _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 4S R 1W	L-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN
 JACKSON COUNTY
 RECORDED

30 DEC 94 3:30 P.M.

GERALD J. McDEVITT
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, John E. Maxson in a field survey on 4 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2, above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

POST SET IN ORIGINAL GOVERNMENT SURVEY BY JOSEPH WAMPLER 1823
 16"W.Oak, N70W, 70 lks (46.20 ft) - 16"W.Oak, N50W, 59 lks (38.94 ft)
 DOUGLAS W. HOOTH, RLS#7966 RECORDED CORNER IN JUNE 1977 (LIBER 3, PAGE 65)
 AS 3/4" IRON BAR
 36"Oak, S63W, 36.98' - 30"Oak, North, 36.79' - 12"Walnut, N35W, 36.97' -
 25"Oak, N65W, 65.74'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON AS RECORDED OVER STONE AND ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER. REPLACED WITH STANDARD 4" CONCRETE MONUMENT AND CAP

SURVEY &
 REMONUMENTATION

MAY 08 1995

COMMISSION

\$ 2.00 REMONUMENTATION

\$ 7.00 CORNER REMONUMENTATION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 4" DIAMETER CONCRETE MONUMENT WITH JACKSON COUNTY REMONUMENTATION.
 CAP STAMPED LS#27454
 N20W 24.45' NAIL IN 26"OAK
 N08E 36.60' NAIL IN 38"OAK
 N23E 34.70' NAIL IN FENCE POST
 S64W 43.94' NAIL IN 12"HICKORY
 N34W 36.98' NAIL IN 14"WALNUT
 EAST 37.48' 3/4 IRON AT L-1, T5S-R1W



Signed by John E. Maxson
 Surveyor's Michigan License No. 27454

Date 8 December, 1994