

**JACKSON COUNTY
APPROVED LAND CORNER**

P.A. 345 of 1990

Acting Chairman *David E. Eickman*

Date Nov. 18, 1998

NORTH $\frac{1}{4}$ POST SECTION 5
NAPOLEON TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
JACKSON
(County)

Located In: Corner Code #

1. Public Land Survey

T 4 S R 2 E

D-1

2. Property Controlling
in Section

S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___



2099413
Page: 1 of 2
12/23/1998 11:22A
L-1589 P-645

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

DEAN R. GUTEKUNST

September 25, 19 97

I, DEAN R. GUTEKUNST, in a field survey on September 25, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set in original Government survey.

Perpetuation by H. F. Bean, no date.

B. Oak 20" N 54 E 97 $\frac{1}{2}$ links (64.35')

B. Oak 18" N 17 W 58 $\frac{1}{2}$ links (38.61')

Perpetuation by W. G. Fargo is 5 links West of H. F. Bean's

B. Oak 20" N 55 E 102 $\frac{1}{2}$ links (67.65')

R. Oak 20" N 12 $\frac{1}{2}$ W 57 $\frac{1}{2}$ links (37.95')

No description

North line Section = 80.40

North line Section 5 = 80.39 $\frac{1}{2}$

Continued on back,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron in blacktop from above information.

Backhoe excavation of the area did not reveal any additional information.

Corner is 3 $\frac{1}{2}$ ' \pm South of the center line of blacktop (Sharon Valley Road) and 12' \pm West of the center line of blacktop (Wolf Lake Road).

Accepted iron and method of establishment as the best position of this corner.

Set a Standard Jackson County Monument to replace iron.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 T4S, R2E

Corner is a 4" diameter X 30" Cast Iron Harrison monument with Brass cap stamped 1S 18658, which is a standard monument for Jackson County

- * S 49 W 33" Oak 45.23' Found 40d nail on Northwest side.
 - ** S 82 $\frac{1}{2}$ W 28" Maple 156.85' Pole barn spike and washer on North side.
 - N 78 $\frac{1}{2}$ W 16" Hickory 142.05' Found 40d nail on South side.
 - N 71 E 9" Hickory 167.75' Pole barn spike and washer on Southeast side.
 - S 68 W 23" Oak 75.17' Found 40d nail on Southeast side.
 - West South $\frac{1}{4}$ Post of Section 32, T3S, R2E (Harrison monument) 222.81'
- Monument box set over monument by Jackson County Road Commission.

Signed by *Dean R. Gutekunst*

Date November 1, 1998

Surveyor's Michigan License No. 18658

Continued,

- A.) - Corner was established by Richard E. Gutekunst, RLS #7863 on August 11, 1965, halfway and on line between the Northwest corner and the Northeast corner of Section 5. NOTE: The Southeast corner of Section 32 was found in September 1997, on this line, and the South $\frac{1}{4}$ post of Section 32 was not found, but set on this line.

Set iron in blacktop.

| | | |
|----------------------|-------------|---------|
| * S 49 W | 24" Oak | 44.36' |
| S 32 W | 20" Oak | 56.00' |
| ** S 81 W | 20" Maple | 156.87' |
| N 74 E | 18" Hickory | 124.30' |
| S 82 $\frac{1}{2}$ E | 15" Maple | 157.61' |

4.7 $\frac{1}{2}$ South of center of blacktop (Sharon Valley Road)

In line of West edge of blacktop South (Wolf Lake Road)

- Not recorded in P.A. 74 .



Mindy Reilly - Jackson Co.

CORREM

2099413

Page: 2 of 2

12/23/1998 11:22A

L-1589 P-645