

**JACKSON COUNTY
APPROVED LAND CORNER
P.A. 345 of 1990**

NORTHEAST CORNER, SECTION 5
NAPOLEON/NORVELL TOWNSHIP

Acting Chairman David R. Gutterman
Date Aug 12, 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

For corners in
JACKSON
(County)

Located in: Corner Code E-1

JAN 27 1999

1. Public Land Survey T 4 S R 2 E
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____



2085644
Page: 1 of 1
08/31/1998 12:
L-1579 P-6

SECTION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DEAN R. GUTEKUNST in a field survey on September 24 & 25, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Hervey Parke, Deputy Surveyor, February 1824.
B. Ash 10" N 58 W 24 links (15.84') 81.80' intersect North boundary
B. Ash 10" S 88 E 13 1/2 links (8.91') 346 links East of post.
Perpetuation by H.F. Bean, no date.
* Elm 14" S 12 3/4 W 76 links (50.16') Found fireclay post and stake at
B. Ash 8" S 51 3/4 W 115 links (75.90') corner for Norvell, set by B.F. LaR

Continued on back,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron in monument box, over large top Fireclay, from above information.
Corner is 1 1/2' ± South of center line of Sharon Valley Road (blacktop) and in line of fence South.
Accepted Fireclay as a careful and faithful perpetuation of the position of the original corner.
Set a Standard Jackson County Monument on top of the Fireclay.
Corner is on Town Line.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 T4S, R2E Corner is a 4" diameter X 30" Cast Iron Harrison monument with a Brase cap stamped LS 18658, which is a standard monument for Jackson County.
*** S 12 W 18" Oak 46.78' Pole barn spike and washer on East side.
S 80 W 8" Maple 155.30' Pole barn spike and washer on North side.
N 25 W 14" Maple 68.97' Pole barn spike and washer on East side, in clump of 7.
N 65 E 14" Maple 83.66' Pole barn spike and washer on North side, in clump of 3.
S 77 E 11" Oak 177.38' Pole barn spike and washer on South side.
West Southeast corner of Section 32, T3S, R2E 227.95' (346 links - 228.36' record
South Steel post and survey marker sign attached 30'
Monument box set over monument by Jackson County Road Commission.

Signed by Dean R. Gutekunst Date August 1, 1998
Surveyor's Michigan License No. 18658

Continued,

- A.) - Perpetuation by H. F. Bean, no date.
- | | | | | |
|-----|-------------|----------------------|---------------------------------|---------------------|
| ** | Hickory 4" | S 72 $\frac{1}{2}$ E | 302 links (199.32') | (Dying August 1998) |
| *** | Swp. Oak 3" | S 11 $\frac{1}{2}$ W | 71 $\frac{1}{2}$ links (47.19') | |
| * | Elm 14" | S 11 $\frac{1}{2}$ W | 76 links (50.16') | |
- P.A. - 74, recorded by Richard E. Gutekunst, RLS #7863, dated April 29, 1976, in LCRC, Liber 2, Page 569, Jackson County Records.
- Found Fireclay, 2.4' below surface, August 4, 1965.
- Set 1" X 2.4' iron on top of fireclay to surface.
- | | | | |
|-----|--------|-----------------------------------|---------|
| *** | S 10 W | Nail in East face of 14" Swp. Oak | 47.02' |
| | North | Nail in West face of 14" Ash | 64.93' |
| | S 70 W | Nail in North face of 24" Ash | 131.31' |
| ** | S 70 E | 18" Hickory | 200.22' |



Mindy Reilly - Jackson Co.

CORREN

2085844
 Page: 2 of 2
 08/31/1998 12:50P
 L-1578 P-689

SURVEY &
 REMONUMENTATION

JAN 27 1999

SECTION