

**JACKSON COUNTY**  
**APPROVED LAND CORNER**  
**P.A. 345 of 1990**

Chairman [Signature] East One Quarter Corner of Section 5, Napoleon Township

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Date Nov. 18, 1998

For corners in JACKSON Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- 1. Public Land Survey T 4S R 2E \_\_\_\_\_ E-2 \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_



2895599  
 Page: 1 of 1  
 11/20/1998 03:25P  
 L-1586 P-917

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on December 19, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Around 1824, H. Parke - Deputy Surveyor, set a "Post" and recorded two witnesses: "W. Oak 10, N76° W, 33" (21.78") and "do 18, N18° E, 64" (42.24').

In the 1880's, a Remonumentation Surveyor notes: "Found fireclay post Set for Norvell - Correct" and recorded three witnesses: "Elm 15, S82°E, 79 1/2" (52.47'); B. Cherry 14 N2° E, 131 (not marked)" (86.46'); Three trunk Maple (middle of three) S2° W, 472" (311.52').

In 1976, R. E. Gutekunst, RLS #7863 recorded the corner as "Found fireclay 8" below surface (10/6/71), 1.7' West of North and South fence, in line fence East 3/4" Iron on Southwest side Fireclay near top of Fireclay 3/4" solid iron on North side of Fireclay to surface" and notes four witnesses: Nelly (13' East of N & S fence) 4" Walnut, 75.10 to center; N45° ± E, 2" Maple, 88.5 to center; S45° ± E, 10" Swp. Oak, 248.8; South, Iron on centerline Austin Road, 602.70' per Land Corner Recordation Certificate (LCRC) recorded in Liber 2, Page 570.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found intact Fire Clay (FC). Also found a 3/4" x 1.89' rebar on North and a 3/4" x 18" Iron Pipe (IP) on Southwest side of FC. Found pieces of brick around base of FC. Accepted found FC as a careful and faithful perpetuation of the original corner. Replaced FC with a standard Jackson County Concrete Monument. Buried FC and irons on North side of monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 36" long concrete monument with iron rod and Standard Jackson County Aluminum Cap stamped "E-2, T4S-R2E, LS #29245".

South	Set, nail and tag #29245, West Side Fence Post	6.25'
N 13° E	Set, nail and tag #29245, West Side 13" Walnut	74.87'
N 56° E	Set nail and tag #29245, West Side 7" Oak	88.51'
S 46° E	Set nail and tag #29245, North Side 20" Oak	248.78'
East	County Surveyor sign post	1.0'

Note: Bearings are Magnetic

Signed by David Erickson Date 11-18-98

Surveyor's Michigan License No. 29245

