

JACKSON COUNTY APPROVED LAND CORNER

NORTH 1/4 POST SECTION 4 NORVELL TOWNSHIP

P.A. 385 of 1990 Acting Chairman David E. Erickson

Date Nov. 18, 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in JACKSON (County)

1. Public Land Survey

T 4 S R 2 E

Corner Code # F-1

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R



2089414 Page: 1 of 2 12/23/1998 11:22A L-1589 P-646

Mindy Reilly - Jackson Co.

CORREN

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

Grid table with columns A-M and rows 2-13. Cell E4 contains a circled '4'.

I, DEAN R GUTEKUNST in a field survey on September 25, 1997

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set in original Government survey.

Information, no name, no date, no description.

Hickory 6" N 3 1/2 E 45 links (29.7')

Corner was established by Richard E. Gutekunst, HLS #7863, on December 15, 1973, halfway between the Northwest corner and Northeast corner of Section 4 and on line of the South 1/4 Post and Southeast corner of Section 33, T3S, R2E. Set 3/4" X 15" capped iron.

Continued on back,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron in blacktop from above information.

Backhoe excavation of the area did not reveal any additional information. Road appears to have been cut approximately 2'

Corner is approximately on center line of blacktop (Sharon Valley Road) and there is no occupation North or South.

Accepted iron and method of establishment as the best position of this corner.

Set a Standard Jackson County Monument to replace iron.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 T4S, R2E Corner is a 4" diameter X 30" Cast Iron Harrison monument with a Brass cap stamped LS 18658, which is a standard monument for Jackson County.

- N 20 W 8" Maple 38.57' Pole barn spike and washer on East side,
N 80 W 3- 24" Oak 124.34' Pole barn spike and washer on South side.
S 55 W 16" Elm 64.74' Pole barn spike and washer on North side.
S 70 E 7" Oak 102.81' Pole barn spike and washer on North side.
West South 1/4 Post of Section 33, T3S, R2E (Harrison Monument) 243.62'
South Steel post and survey marker sign attached 28.4'±
Monument box set over monument by Jackson County Road Commission.

Signed by Dean R. Gutekunst

Date November 1, 1998

Surveyor's Michigan License No. 18658

Continued,

A.) - N 5 E 12" Hickory 32.58'
N 45 W 18" Oak 39.28'
S 45 W Northeast corner of foundation house #11523 131.78'
West South $\frac{1}{4}$ Post of Section 33, T3S, R2E 243.53' (fireclay)

- Not recorded in P. A. 74



Mindy Reilly - Jackson Co.

CORREM

2899414

Page: 2 of 2

12/23/1998 11:22A

L-1589 P-846