

A-8/13/97

JACKSON COUNTY  
APPROVED LAND CORNER  
P.A. 343 of 1998  
ACTING  
Chairman  
Timothy B. Van Sledright  
Date 08-13-97

WEST 1/4 POST, SECTION 11  
NORVELL TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

#2058027  
Liber 1559 Page 84  
Page 1 of 2  
Jackson Co., MI  
Recorded  
01/07/1998 03:50P  
Mindy Reilly  
Register of Deeds

For corners in  
JACKSON  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 4 S R 2 E	I-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

SURVEY & REMONUMENTATION

SEP 16 1998

Register of Deeds Stamp & File Number

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, DEAN R. GUTEKUNST in a field survey on JUNE 9 19 97 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Hervey Parke, Deputy Surveyor, 1824.  
W. Oak 40" S 70 E 147 links (97.02')  
Y. Oak 6" N 50 1/2 W 64 links (42.24')  
Perpetuation by B. F. LaRue, November 8, 1884.  
B. Oak 12" N 45 3/4 W 62 1/2 links (41.085')  
\* Maple 6" N 87 E 42 links (27.72')

Iron stake set by P.T. Cook from remains of witness. I found traces of 1 witness, and lime.

Continued on back,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found bottom 12" of Fireclay, with lime under, and an iron on top to surface.  
Corner is 5'± West of center line of Fay Lake Road (blacktop) and in line with hedge row East and West.

Accepted Fireclay as a careful and faithful perpetuation of the position of the original corner as remonumented by LaRue in 1884.

Set a Standard Jackson County Monument to replace the Fireclay and left fireclay buried beside the monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


\*\*\* N 35° E 30" Maple 50.79' Found 60d on Southeast side.  
\*\*\*\* S 35° W 31" Maple 42.60' Found 60d on Northwest side.  
N 20° W 7" Triple Maple 70.58' Pole barn spike and washer on East side.  
\*\*\*\*\* S 35° E 39" Maple 48.38' Pole barn spike and washer on Southwest side.  
S 85° E 27" Maple 84.24' Found 60d on South side.  
S 85° W East face 2" steel post of 4' chain link fence 29.45'  
West Double 2" Walnut 29.0' no nail  
West Steel post and survey marker sign attached 27.8'

Monument box set by the Jackson County Road Commission.

Continued on back,

Signed by Dean R. Gutekunst  
Surveyor's Michigan License No. 18658

Date August 1, 1997



Continued,

I-4

T4S, R2E

A.) - Perpetuation by Fred C. Riley, #377, dated May 29, 1933.  
Fireclay post, 1' below surface.

**	Maple 28"	S 85 W	22.30'	
***	Maple 25"	N 43 30 E	50.50'	
****	Maple 19"	S 32 30 W	42.10'	
*****	Maple 28"	S 33 30 E	47.10'	
*	Maple 29"	S 89 30 E	26.95'	

- Perpetuation by Richard E. Gutekunst, RLS #7863, dated 1964 and 1973.  
Found Fireclay 24" below surface.

Set iron on top.

**	Maple 28"	S 85 W	23.0'	stump 1997
***	Maple 25"	N 43 30 E	50.85'	
****	Maple 19"	S 32 30 W	42.76'	
*****	Maple 28"	S 33 30 E	48.38'	
*	Maple 29"	S 89 30 E	27.98'	

- Not recorded in P.A.-74.

C.) - I-4 T4S, R2E Corner is a 4" diameter X 30" Cast Iron Harrison monument with a brass cap stamped LS 18658, which is a standard monument for Jackson County.

SURVEY &  
REMONUMENTATION

SEP 16 1998

SECTION