

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

#2022468
 Liber 1533 Page 348
 Page 1 of 2
 Jackson Co., MI
 Recorded
 12/12/96 01:03P
 Jerry McDewitt
 Register of Deeds

For corners in
JACKSON
 (County)

| | Located In: | Corner Code =# |
|------------------------------------|---------------------------|----------------|
| 1. Public Land Survey | T <u>4</u> S R <u>2</u> E | I-10 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | ⊕ | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, DEAN R. GUTEKUNST, in a field survey on November 14, 19 96
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Hervey Parke, Deputy Surveyor, Feb. 1824,
 W. Oak 26" S 26 E 179 links (118.14')
 Tamarack 6" N 40 W 42 links (27.72')
 Perpetuation by B. F. LaRue, November 22, 1884
 Double R. Oak 5" South 432 links (285.12')
 Y. Oak 1" S 76 1/2 W 45 3/4 links (30.195')
 * Tamarack 8" N 88 3/4 E 108 1/2 links (71.61')

Found stump of one witness, blaze distinct and remains Tamarack witness agreeing. Broken Fireclay

Continued on back,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found FIRECLAY under 12" of water with capped iron on South side and rusted off steel post on North side.

Corner is Approximately 1' South of East & West fence. No occupation North or South at corner.


Accepted FIRECLAY as a careful and faithful perpetuation of the position of the original corner, as remonumented by LaRue in 1884.

Set a 1" X 60" aluminum pipe with cap to replace fireclay and left fireclay buried on West side of pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 T4S, R2E Corner is a 1" X 60" aluminum pipe with an aluminum cap stamped IS 18658, which is a standard monument for Jackson County, in low marshy areas.

| | | | |
|---------|--|---------|---------------------------|
| S 10° E | 20" Cherry | 96.40' | 40d & washer on East side |
| S 55° W | 18" Oak | 200.05' | center line |
| West | 24" Cherry | 390.00' | center line |
| West | RR tie corner post (fences East, West & South) | 389.27 | |
| North | Steel post and survey marker sign attached | 0.5' | |



Signed by *Dean R. Gutekunst* Date November 30, 1996
 Surveyor's Michigan License No. 18658

Continued,

I-10 T4S, R2E

A.) - Information from the Jackson County Road Commission, no date

| | | | |
|-------------|-----------|---------|----------|
| Twin R. Oak | S 5 W | 285.12' | Fireclay |
| 12" Y. Oak | S 76 30 W | 30.2' | |
| * Tamarack | N 88 45 E | 71.61' | |

- Perpetuation by Richard E. Gutekunst, RLS #7863, on November 18, 1967 and recorded in LCRC, Liber 1, Page 623, Jackson County Records, under P A.-74.

Found fireclay and one witness*)(stump 9/1/72)

Set iron on North side of fireclay and metal post on North side.
Set capped iron on South side of fireclay (9/1/72/)

| | | |
|--------|--------------------|---------|
| S 10 E | 8" Cherry | 96.4' |
| SWly | 15" Oak | 200.05' |
| West | RR tie corner post | 389.27' |
| West | 15" Cherry | 390.0' |

- P A. 74, recorded by Kenneth L. Suydam, RLS #17636, dated March 10, 1978 in LCRC, Liber 3, Page 131, Jackson County Records.

Found iron pipe

| | | |
|------------|--------------------|---------|
| N 40 W | 6" Tamarack | 27.72' |
| West | RR tie corner post | 389.27' |
| S 76 30 W | 1" Yellow Oak | 30.20 |
| SWly | 15" Oak | 200.05' |
| South | 5" Double Oak | 285.12' |
| S 10 E | 8" Cherry | 96.4' |
| S 26 E | 26" W. Oak | 118.14' |
| N 88 3/4 E | 8" Tamarack | 71.61' |