

JACKSON COUNTY
APPROVED LAND CORNER
P.A. 345 of 1996
 Acting
 Chairman
 Timothy O. VanGieson
 Date 08-13-97

NORTH $\frac{1}{4}$ POST, SECTION 14
 NORVELL TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

#2044412
 Liber 1549 Page 132
 Page 1 of 2
 Jackson Co., MI
 Recorded
 08/15/97 10:54A
 Mindy Reilly
 Register of Deeds

For corners in
JACKSON

(County)

Located in:

Corner Code #

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>4</u> S R <u>2</u> E	J-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5					⊙								
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

DEAN R. GUTEKUNST, in a field survey on JULY 30, 1997

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

Original Government post set by Hervey Parke, Deputy Surveyor, February 1824.

Elm 14" S 73 E 5 links (3.30')

Elm 24" N 80 W 21 links (13.86')

Perpetuation by B. F. LaRue, December 11, 1884.

W. Oak 14" S 87 $\frac{1}{2}$ E 59 $\frac{3}{4}$ links (39.435')

W. Oak 4" S 17 E 34 links (22.44')

W. Oak 5" S 11 $\frac{1}{2}$ W 42 links (27.72')

Maple 7" S 29 W 50 $\frac{1}{2}$ links (33.33')

Found Post as established by P.T. Cook, moved this S 28 $\frac{1}{2}$ W 2 links because I had moved the Section corner $\frac{1}{2}$ mile West S 28 $\frac{1}{2}$ W 4 links from where Cook located it.

Continued on back,

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Fireclay with a $\frac{1}{2}$ " iron on North side and a capped (#7863) iron ^{on} East side. Also found second Fireclay under surface fireclay.

Accepted Fireclay as a careful and faithful perpetuation of the position of the original corner as remonumented by LaRue in 1884.

Set a Standard Jackson County Monument to replace the Fireclay and left fireclay pieces buried around monument.



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 T4S, R2E Corner is a 4" diameter X 36" concrete monument with a $\frac{1}{2}$ " X 36" steel rod and an aluminum cap stamped LS 18658, which is a standard monument for Jackson County.

****	S 75° E	16" Beech	47.87'	Pole barn spike and washer on South side.
****	S 60° W	9" Birch	6.85'	Found 40d and cap on North side.
****	S 20° E	18" W. Oak	22.74'	Pole barn spike and washer on East side.
**	N 10° E	18" Oak	5.8'	Found 40d and cap on Southeast side.
***	S 20° W	30" Oak	15.08'	Pole barn spike and washer on Northwest side.
*	S 50° E	18" W. Oak	10.14'	Found 40d and cap on Northeast side.
	South	Steel post and survey marker sign attached	2'	

igned by Dean R. Gutekunst Date August 1, 1997
 Surveyor's Michigan License No. 18658

Continued,

J-5

T4S, R2E

A.) - Perpetuation by Fred C. Riley, #377, dated May 26, 1932.

Found Fireclay

*	W. Oak	7"	S 48 E	10.20'	OK 1965
	Maple	12"	S 10 W	46.93'	
	Maple	14"	S 29 W	33.00'	

- Perpetuation by Richard E. Gutekunst, RLS #7863, dated January 1965.

Found Fireclay, set $\frac{1}{2}$ " iron of North side.

**	N 10 E	12" Oak	5.9'
***	S 20 W	24" Oak	15.94'

- Perpetuation by Richard E. Gutekunst, RLS #7863, dated April 6, 1974.

Found Fireclay with iron on North side.

Set capped iron (#7863) on East side.

**	N 5 E	14" Oak	5.8'
*	S 40 E	18" W. Oak	10.13'
	S 45 E	20" Maple	36.77'
	South	12" Oak	22.79'
***	S 30 W	24" Oak	15.23'

- Perpetuation by Richard E. Gutekunst, RLS #7863, dated February 23, 1984.

Found Fireclay with $\frac{1}{2}$ " iron on North side and capped iron (#7863) on East side.

Corner is at bottom of hill and 5'± South of marsh.

	S 75 E	11" Beech	62.10'
*****	S 55 W	7" Birch	6.89'
****	S 20 E	16" W. Oak	22.72'
**	N 10 E	12" Oak	5.81'
***	S 20 W	24" Oak	15.16'
*	S 40 E	18" W. Oak	10.13'

- Not recorded in P. A. - 74.