

**JACKSON COUNTY**  
**APPROVED LAND CORNER**  
**P.A. 345 of 1990**

EAST  $\frac{1}{4}$  POST, SECTION 26  
 NORVELL TOWNSHIP

Chairman David E. Erickson  
 Date 5-15-97

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

#2035223  
 Liber 1542 Page 571  
 Page 1 of 2  
 Jackson Co., MI  
 Recorded  
 05/15/97 11:31A  
 Mindy Reilly  
 Register of Deeds

For corners in  
JACKSON  
 (County)

Located in:

Corner Code #

**SURVEY &  
 REMONUMENTATION**

1. Public Land Survey T 4 S R 2 E  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

K-10  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 2. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

DEAN R. GUTEKUNST, in a field survey on November 22, 1996, 19\_\_\_\_,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Hervey Parke, Deputy Surveyor, February 1824.

- Y. Oak 14" N 73 E 33 links (21.78')
- Y. Oak 18" S 19 W 17 $\frac{1}{2}$  links (11.55')
- Perpetuation by B. F. LaRue, November 20, 1884.
- \* W. Oak 13" N 11 $\frac{1}{2}$  W 121 $\frac{1}{2}$  links (80.19')
- \*\* W. Oak Double S 10 W 127 $\frac{1}{2}$  links (84.15')

Found good traces of both witness trees and of stake agreeing. Lime.

Continued on back,

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found broken FIRECLAY from above information.

Corner is 6'± West of center line of Lawrence Road (gravel).

Accepted FIRECLAY as a careful and faithful perpetuation of the position of the original corner, as remonumented by LaRue in 1884.

Set a Standard Jackson County Monument to replace the fireclay and left fireclay buried on the North and West side and two irons on the South side of the monument.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 T4S, R2E

Corner is a 4" diameter X 36" concrete monument with a  $\frac{1}{2}$ " X 36" steel rod and an aluminum cap stamped LS 18658, which is a standard monument for Jackson County.

- \* N 11 $\frac{1}{2}$ ° W 44" Oak 80.06' 40d & washer on East side.
- \*\* S 10° W 42" Oak 84.48' 40d & washer on East side.
- \*\*\*\*\* N 41° W 14" Walnut 33.40' 40d & washer on Northeast side
- S 80° E 12" Walnut 43.05' 40d & washer on North side.
- N 30° E 8" Walnut 56.67' 40d & washer on North side.

West Steel post and survey marker sign attached 25.0'

signed by Dean R. Gutekunst

Date May 1, 1997

Surveyor's Michigan License No. 18658



Continued,

K-10

T4S, R2E

- A.) - P.A. -74, recorded by Richard E. Gutekunst, RLS # 7863, dated December 28, 1972, in LCRC, Liber 1, Page 627, Jackson County Records.

Found broken fireclay with lime underneath.  
Set capped iron on South side of fireclay.

|              |  |         |       |
|--------------|--|---------|-------|
| * N 11½ W    | 36" W. Oak                                   | 80.38'  |       |
| ** S 10 W    | W. Oak Double                                | 84.37'  |       |
| *** N 9 E    | 28" Oak                                      | 133.80' |       |
| **** N 83 E  | 14" Cherry                                   | 67.07'  |       |
| ***** N 41 W | 6" Walnut                                    | 34.16'  |       |
| ***** S 37 W | Southeast corner of stone foundation of Barn |         | 81.2' |

- P A. - 74, recorded by Kenneth L. Suydan, RLS # 17636, dated March 22, 1978, in LCRC, Liber 3, Page 132, Jackson County Records.

Found iron

|                             |        |        |          |
|-----------------------------|--------|--------|----------|
| * 36" W. Oak                | N 11 W | 80.38' |          |
| ***** 6" Walnut             | N 41 W | 34.16' |          |
| ***** Southeast corner barn | S 37 W | 81.20' |          |
| ** Double W. Oak            | S 10 W | 84.37' |          |
| **** 14" Cherry             | N 83 E | 67.07' |          |
| *** 28" Oak                 | N 9 E  | 13.38  | (133.8') |