

JACKSON COUNTY
APPROVED LAND CORNER
P.A. 345 of 1990
 ACTING
 Chairman
 Date 12-11-96

NORTH 1/4 POST, SECTION 25
 NORVELL TOWNSHIP

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

#2022466
 Liber 1533 Page 346
 Page 1 of 2
 Jackson Co., MI
 Recorded
 12/12/96 01:02P
 Jerry McDevitt
 Register of Deeds

For corners in
JACKSON
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>4</u> S R <u>2</u> E	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

I, DEAN R. GUTEKUNST, in a field survey on November 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5						3		2			
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Hervey Parke, Deputy Surveyor, February 1824.
 B. Oak 18" S 2 E 50 links (33.0')
 W. Oak 36" N 48 W 56 links (36.96')
 Perpetuation by B. F. LaRue, December 6, 1884
 W. Oak 5" N 82 1/2 W 9 1/4 links (6.105')
 * W. Oak 6" S 64 W 30 3/4 links (20.295')
 W. Oak 36" (original) N 48 W 56 links (36.96')

Found 1 witness standing and stump of other witness, and good remains of stake.
 Broken Fireclay.

Continued on back,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found FIRECLAY, broken into 4 pieces, including bottom but no top, and capped iron from above information.
 Corner is 1.2' East of the North & South fence, 0.3' North of the old fence East and 10.7' North of the fence line running West.
 Accepted FIRECLAY as a careful and faithful perpetuation of the position of the original corner, as remonumented by LaRue in 1884.
 Set a Standard Jackson County Monument to replace the fireclay and left fireclay buried around monument and iron buried on the West side of monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 T4S, R2E Corner is a 4" diameter X 36" concrete monument with a 1/2" X 36" steel rod and an aluminum cap stamped LS 18658, which is the standard monument for Jackson County.

- * S 70° W 25" Oak 21.21' 40d & washer on North side
- ** N 40° W 23" Oak 29.20' Found double headed nail & cap on South side
- *** N 80° W 22" Oak 23.71' 40d & washer on North side
- N 10° E 14" Hickory 13.43' 40d & washer on West side
- S-60° E 16" Oak 32.78' 40d & washer on South side
- S 50° E 22" Hickory 39.41' 40d & washer on East side
- West Steel post and survey marker sign attached 1.5'



Signed by Dean R. Gutekunst Date November 30, 1996
 18658

Surveyor's Michigan License No. _____