

**JACKSON COUNTY**  
**APPROVED LAND CORNER**  
**P.A. 345 of 1990**  
 ACTING  
**Chairman**  
 Timothy B. VanGrison  
 Date 08-13-97

EAST 1/4 POST, SECTION 24  
 NORVELL TOWNSHIP

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

#2044408  
 Liber 1549 Page 128  
 Page 1 of 1  
 Jackson Co., MI  
 Recorded  
 08/15/97 10:48A  
 Mindy Reilly  
 Register of Deeds

or corners in  
**JACKSON**  
 (County)

Located in: \_\_\_\_\_ Corner Code # M-8  
 T 4 S R 2 E  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY & REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 16 | 17 | 18 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

**DEAN R. GUTEKUNST**, in a field survey on April 14, 97 & June 9 97, 19 \_\_\_\_\_

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- Original Government Post set by Benjamin Hough, Deputy Surveyor, 1815-1816.
  - B. Oak 16" S 68 1/2 W 49 1/2 links (32.67')
  - B. Oak 24" S 17 E 65 1/2 links (43.23')
- Perpetuation by B. F. LaRue, November 18, 1884.
  - Hickory 12" S 33 1/2 E 81 links (53.46')
  - \* Hickory 12" S 60 3/4 W 53 1/4 links (35.145')

Found stake from remains of witnesses by O. Curtis, 1852.  
 -- Broken Fireclay --  
 Found slight traces of Government witnesses.

Not recorded in P. A. - 74.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Fireclay, top 3" broke off in backhoe excavation. Balance of Fireclay is in two pieces. Found two handfuls of broken fireclay under bottom of fireclay.

Corner is 3'± West of center line of Watkins Road (blacktop).

No Occupation East or West at corner.

Accepted Fireclay as a careful and faithful perpetuation of the position of the original corner as remonumented by LaRue in 1884.

Set a Standard Jackson County Monument to replace fireclay and left broken fireclay pieces under monument and two pieces of fireclay buried on Northeast and Southeast side of monument.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 T4S, R2E Corner is a 4" diameter X 30" Cast Iron Harrison monument with a brass cap stamped IS 18658, which is a standard monument for Jackson County.

- \* S 65° W 32" Hickory 35.69' Pole barn spike and washer on North side.
- S 15° W 21" Hickory 83.95' Pole barn spike and washer on West side.
- N 70° E 15" Hickory 33.65' Pole barn spike and washer on North side.
- S 25° E 19" Osage Orange 61.51' Pole barn spike and washer on West side.
- West Steel post and survey marker sign attached 22'

Monument box set by the Jackson County Road Commission.

Recorded by Dean R. Gutekunst  
 Surveyor's Michigan License No. 18658

Date August 1, 1997

