

**JACKSON COUNTY**  
**APPROVED LAND CORNER**  
**P.A. 345 of 1990**

ACTING  
 Chairman David E. Erickson  
 Date 7-9-97

SOUTH  $\frac{1}{4}$  POST, SECTION 32  
 HANOVER TOWNSHIP

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

#2040666  
 Liber 1546 Page 462  
 Page 1 of 2  
 Jackson Co., MI  
 Recorded  
 07/09/97 01:13P  
 Mindy Reilly  
 Register of Deeds

For corners in  
JACKSON  
 (County)

Located In:	Corner Code #
T <u>4 S</u> R <u>2 W</u>	D-13
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

**SURVEY & REMONUMENTATION**

APR 07 1998

**SECTION**

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**DEAN R. GUTEKUNST**

May 8, 1997 & June 11, 1997

in a field survey on \_\_\_\_\_, 19\_\_\_\_  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Original Government Post set by Joseph Wampler, Deputy Surveyor, 1823.  
 W. Oak 9" N 54 E 17 links (11.22')  
 W. Oak 8" N 82 W 52 links (34.32')  
 Perpetuation by H. F. Bean, 1886.  
 W. Oak 20" S 71 $\frac{1}{4}$  E 197 $\frac{1}{2}$  links (130.35')  
 Y. Oak 24" N  $\frac{1}{4}$  E 189 $\frac{1}{2}$  links (125.07')

Post out, run and measured the line and found remains of witnesses.

Continued on back,

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found FIRECLAY 12" below surface of Weir Road (gravel).  
 Found Stone on top of fireclay and broken brick around.  
 Corner is approximately 2' North of center line of gravel.  
 No occupation North.  
 Approximately 108' West of hedge row South.  
 Also found cluster of 6 -  $\frac{1}{2}$  brick pieces, 5.0' South and 5.8' East.  
 Accepted FIRECLAY, as a careful and faithful perpetuation of the position of the original corner as remonumented by H. F. Bean in 1886.  
 Set a Standard Jackson County Monument to replace the fireclay and left fireclay buried on the North side of the monument and the brick pieces under the monument.



**Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

D-13 T4S, R2W Corner is a 4" diameter X 30" Cast Iron Harrison monument with a brass cap stamped LS 18658, which is a standard monument for Jackson County.

N 50° W	28" Oak	40.87	5" Pole barn spike and washer on Southwest side.
N 20° E	14" Walnut	25.88'	5" Pole barn spike and washer on East side.
N 70° E	16" Walnut	86.90'	5" Pole barn spike and washer on North side.
S 80° W	15" Oak	126.27'	5" Pole barn spike and washer on North side.
N 70° W	9" Walnut	92.45'	5" Pole barn spike and washer on North side.
North	Steel post and survey marker sign attached	25.0'	

Signed by Dean R. Gutekunst  
 Surveyor's Michigan License No. 18658

Date July 1, 1997