

Chairman Alan R. Rutledge
 Date Dec. 21, 1998

East 1/4 Corner of Section 33, Hanover Township

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in JACKSON Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 4S R 2W _____ G-12
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____



2099100
 Page: 1 of 1
 12/21/1998 11:55A
 L-1589 P-342

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on December 17, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In 1825, Robert Clark, Jr. - Deputy Surveyor, set a "Post" and recorded two witnesses: "Hick 7, N14° W, 2" (1.32') and "Hick 10, S 13° W, 50" (33.00').

In 1886, H.F.Bean reported, "Stone Post, has been kept. Set F.C. Post 1 1/2 Rods West + Stone 1 1/2 Rods East." and recorded two witnesses: "Hickory 10 N 21 1/2 ° E 92" (60.72') and "W. Oak 10 N 88 °E 28" (18.48').

Corner not recorded under P.A. #74

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Railroad Spike with pieces of brick below. Position falls in road cut. Also found lower 7" of FireClay (FC) (leaning East) to West with TVG capped Iron Pipe Leaning over top of FC. Also found large "squarish" 15" stone to East and Also Bean's 2nd Witness. Measured distance between top center of Stone and center of FC, if positioned vertically. Measurement fits original distance of 49.5'. I split this distance and set a standard Jackson County Harrison Cast Iron Monument at this position. Accepted this position as a careful and faithful perpetuation of the original corner. Rejected position of RR Spike, which is S 35° W, 0.32'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Jackson County Harrison Cast Iron Monument stamped "#29245".

N 11° E	Set Nail & Tag #29245 in West side 11" Oak	104.15'
East	Set Nail & Tag #29245 in North side 40" Oak (Beans)	19.29'
S 18° E	Set Nail & Tag #29245 in West side 20" Oak	65.86'
S 37° W	Set Nail & Tag #29245 in Southeast side 20" Oak	49.92'
West	County Surveyor sign post	21.2'
East	Top center of 15" squarish stone	24.75'
West	TVG capped IP leaning East over leaning FC	24.51'

Note: Bearings are magnetic.



Signed by David Erickson Date 12-18-98

Surveyor's Michigan License No. 29245