

**JACKSON COUNTY
APPROVED LAND CORNER
P.A. 349 of 1996**

Chairman David Erickson
Date Sept. 9, 1998

Center of Section 34, Hanover Township
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
REMONUMENTATION**

JAN 27 1999

SECTION

For corners in
JACKSON
(County) Located In: Corner Code #

1. Public Land Survey T4S R2W H-12
T R
T R
T R
T R
2. Property Controlling in Section S T R
S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R



2087053
Page: 1 of 1
09/10/1998 11:0
L-1580 P-53

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David E. Erickson, in a field survey on March 26, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner not set in original government survey of 1825, nor by Bean in 1886.

Not recorded under Public Act 74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Established corner at intersection of quarter lines as defined by remonumented corners. Set a standard aluminum pipe with cap for the corner. A found 1" iron pipe located N38°E, 8.81 feet from established corner was rejected. No record of this iron pipe could be found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3' aluminum rod with Jackson County Survey Monument Cap stamped "H-12, T4S-R2W, LS #29245, 1997".

N 38° E	1" pipe	8.81'
S 82° E	Set nail and tag #29245, South side 8" Oak	10.45'
S 35° W	Set nail and tag #29245, East side 19" Oak	32.26'
N 71° W	Set nail and tag #29245, North side 14" Oak	1.75'
N 23° W	Set nail and tag #29245, Northeast side 10" Oak	41.47'
N 01° W	Set nail and tag #29245, West side 7" Oak	18.68'
West	County Surveyor sign post	1.3'

NOTE: Bearings are magnetic



Signed by David Erickson

Date 9-8-98

Surveyor's Michigan License No. 29245

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1988