

REGISTERED LAND SURVEYOR
 P.A. 895 of 1970
 Clerk *David E. Erickson*
 Date Mar. 11, 1998

North 1/4 Corner of Section 14, Hanover Township
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

#2064448
 Liber 1563 Page 994
 Page 1 of 1
 Jackson Co., MI
 Recorded
 03/12/1998 12:00P
 Ninda Reilly
 Register of Deeds

For corners in JACKSON Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T4S R2W J-5
 T _____ R _____
 T _____ R _____ SURVEY &
 T _____ R _____ REMONUMENTATION

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____ SECTION _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on September 24, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Around 1825, R. Clark Jr. - Deputy Surveyor, reported the corner as "Set Post" and recorded two witnesses: "W. Oak 10, N87°W, 5" (3.30') and "W. Oak 10, N63°W, 5" (3.30').

In 1886, H.F. Bean reported "Both witnesses Standing, found the old stake hole" and recorded two witnesses: "W. Oak 3, S5°W, 81" (53.46') and "Y. Oak 3, S82 1/2°W, 78 1/4" (51.64').

In 1973, R.E. Gutekunst - RLS #7863, recorded the corner as "Found fireclay @ South end of stone row running North. Set capped iron on North side of fireclay. Fence E & W & N." per Land Corner Recordation Certificate (LCRC) recorded in Liber 2, Page 293.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found intact fireclay (FC) with iron pipe with cap "REG 7863" on North side. Also found pieces of broken brick beneath FC. Accepted found FC as a careful and faithful perpetuation of the original corner. Set a standard Jackson County concrete monument in exact position of FC. Buried FC and iron pipe on North side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard concrete monument with aluminum cap stamped "#29245".

S 85° W	Found nail and tag in dead 30" Oak	51.85'
N 14° E	Found 40" dead stump	24.5'
S 72° W	Set nail and tag #29245, South side 8" Black Cherry	5.33'
N 52° W	Set nail and tag #29245, Northeast side 6" White Oak	18.69'
S 88° E	Set nail and tag #29245, South side 18" White Oak	16.32'
S 09° W	Set nail and tag #29245, East side 8" White Oak	21.95'

NOTE: Bearings are magnetic



Signed by David E. Erickson Date 3-11-98

Surveyor's Michigan License No. 29245