

**JACKSON COUNTY
APPROVED LAND CORNER
P.A. 345 of 1990**

N 1/4 CORNER OF SECTION 1, HANOVER TWP.
 Chairman Arden S. Pierson
 Date Dec. 20, 1994

LIBER 1451 PAGE 198

LIBER 1451 PAGE 198

STATE OF MICHIGAN
 JACKSON COUNTY
 RECORDED

**LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
 Jackson

30 DEC 94 11:23 A.M.

GERALD J. McDEVITT
 REGISTER OF DEEDS

_____ (County)	Located in:	Corner Code #/
1. Public Land Survey	T <u>4S</u> R <u>2W</u>	<u>L-1</u>
	T _____ R _____	<u>SURVEY &</u>
	T _____ R _____	<u>REMONUMENTATION</u>
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	<u>MAY 03 1995</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	<u>COMMISSION</u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Arden S. Pierson PS, in a field survey on December 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 L-1 - This position not established by original government surveyors.

\$ 2.00 REMONUMENTATION
 \$ 7.00 CORNER REMONUMENTATION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section 1, Hanover Township

L-1 - Found 3/4" pipe with cap stamped RLS# 7863, and 66.91' East of the standard corner and on the township line. This pipe is accepted as the best available evidence of the position of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**L-1 (N 1/4 corner Section 1)
Jackson County Monument**

Witness sign post set -East- 3.6'
 Nail & tag #13039 in W. side 6" Oak -N15°W- 21.06'
 Nail & tag #13039 in S. side 14" Aspen -N70°W- 39.50'
 Nail & tag #13039 in N. side 11" Oak -N70°E- 34.79'
 Nail & tag #13039 in NE side Wood Anchor post -S65°E- 1.38'
 (STANDARD CORNER IS WEST 66.91')

*Standard Jackson County Monument is a 1/2" iron rod 36" long with a Jackson County Remonumentation disk encased in a 4" concrete cylinder.



Signed by Arden S. Pierson Date December 6, 1994

Surveyor's Michigan License No. 13039