

**JACKSON COUNTY
APPROVED LAND CORNER
P.A. 343 of 1990**

NORTHWEST CORNER, SECTION 31
PULASKI TOWNSHIP

**SURVEY &
REMONUMENTATION**

Chairman Dean R. Gutekunst

Date April 14, 1999

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

MAR 13 2000

For corners in

JACKSON
(County)

Located In:

Corner Code #

SECTION

1. Public Land Survey T 4 S R 3 W A-11
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



2139075
Page: 1 of 1
12/06/1999 03:28P
L-1618 P-939

Register of Deeds Stamp & File Number

I, DEAN R. GUTEKUNST, in a field survey on July 9, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Robert Clark, Jr., Deputy Surveyor, 1825
White Oak 13" N 32 E 36 links (23.76') 80.33 chain intersect West boundary 66 links
White Oak 48" S 76 E 81 links (53.46') (43.56') South of post.

No additional perpetuation has been found.

Not recorded in P.A. - 74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner was established at the record distance 43.56' (66 links) South of the Northeast corner of Section 36, Town 4 South, Range 4 West, Homer Township, Calhoun County, Michigan, (recorded in Liber 1899, Page 611, Calhoun County Records) and on the East line of said Section 36.

Hand excavation at the position did not reveal any additional information about the corner.

Corner is 1' East of center line of blacktop of Van Wert Road and in line of occupation East.

Set a Standard Jackson County Monument for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 T4S, R3W Corner is a 4" diameter X 30" Cast Iron Harrison monument with a Brass cap stamped LS 18658, which is a standard monument for Jackson County.

North	Found Berntsen monument in monument box, set for the Northeast corner of Section 36, T4S, R4W, Calhoun County, Michigan.	43.56'
S 80 W	22" Hickory 54.95'	Pole barn spike and washer on North side.
N 35 W	16" Hickory 83.93'	Found spike and Calhoun County Remon. tag on SW side.
N 10 E	35" Maple 115.76'	Found spike and Calhoun County Remon. tag on West side.
S 10 E	41" Maple 129.32'	Found spike and Calhoun County Remon. tag on West side.
S 10 W	21" Maple 136.98'	Found spike and Calhoun County Remon. tag on East side.
East	Steel post and survey marker sign attached 30'	

Monument box set over monument by the Jackson County Road Commission.

April 1, 1999

Signed by Dean R. Gutekunst

Date

Surveyor's Michigan License No. 18658

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

