

SURVEY & REMONUMENTATION

MAR 13 2000

SECTION

ASSISTANT COUNTY CLERK
P.A. 845 of 1970
Date FEB 10 1999

Southeast Corner of Section 13, Pulaski Township
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in JACKSON (County) Located in: Corner Code #

1. Public Land Survey T 4S R 3W M-7
T _____
T _____
T _____

2. Property Controlling In Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____



2104488
Page: 1 of 1
02/10/1999 10:51A
L-1593 P-262

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David E. Erickson, in a field survey on April 27, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In 1823, J. Wampler - Deputy Surveyor, set a "Post" and recorded two witnesses: "B. Oak 12, S64°W, 26" (17.16') and "do 12, S45°W, 40" (26.40').

This corner not recorded under Act #74.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" iron bar in monument box. Excavated monument box. Below box and iron is a large pointed stone. Amended corner to be on line between M-5, T4S-R3W and A-7, T4S-R2W. A-7 is remonumented (Liber 1482, Page 647) as being on the Township line. The found iron in the box is 0.34' West of the amended position. The amended position is still over the stone found below box. Set a standard Jackson County Harrison Cast Iron Monument on line between remonumented corners M-5 and A-7, over the found stone, 0.34' East of iron, in Monument Box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Jackson County Harrison Cast Iron Monument stamped "M-7, #29245".

S 31° E	Set Nail & Tag #29245 in West side Power Pole	122.41'
S 24° E	Found Nail & Shiner in Northeast side 18" Oak	147.48'
S 27° W	Set Nail & Tag #29245 in East side 20" Cherry	96.40'
S 76° W	Found Nail & Shiner in East side 30" Oak	96.59'
NW'ly	County Surveyor sign post	50.0'

Note: Bearings are magnetic.

N01°45'25"E Corner M-5 as remonumented 5292.26'
S01°45'25"W Corner A-7 as remonumented 95.93' (GLO = 95.7')



Signed by David Erickson Date 2-9-99

Surveyor's Michigan License No. 29245

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971

REVISED MAY 14, 1975
REVISED JAN. 1983
ADAPTED FOR WORD PROCESSING MARCH, 1987