

JACKSON COUNTY
 APPROVED LAND CORNER
 P.A. 345 of 1996
 ACTING Chairman
 Date 12-11-96

SOUTHEAST CORNER, SECTION 36
 FULASKI TOWNSHIP

DUPLICATE OF CORNER
 recorded for the
 Southwest corner of Section
 31, Hanover Township.

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
JACKSON
 (County)
 Located in: Corner Code #
 1. Public Land Survey T 4 S R 3 W M-13
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

#2022475
 Liber 1533 Page 355
 Page 1 of 2
 Jackson Co., MI
 Recorded
 12/12/96 01:08P
 Jerry McDevitt
 Register of Deeds

Register of Deeds Stamp & File Number

I, DEAN R. GUTEKUNST, in a field survey on November 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Post set by Joseph Wampler, Deputy Surveyor, 1823
 W. Oak 14" S 28 W 18 links (11.88') 78.72 chains, Intersect range line
 W. Oak 13" N 7 W 58 links (38.28') 4.80 links South of temp. post.
 Set post corner of Township # 4 & 5 South, Ranges # 2 & 3 West.
 (NOTE: The written notes show South line to be 78.72 chains, GIO map shows 73.72 chains. I think the 78.72 chain distance is a scrivener's error and the correct distance should be 73.72 chains, which Continued on back,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found FIRECLAY, 7" below gravel surface with a 1/2" pinched iron on the South side.
 Corner is approximately 1' East of center line of Grover Road (gravel) and in line with hedge row running West.
 Accepted FIRECLAY, as a careful and faithful perpetuation of the position of the original corner as remonumented by H. F. Bean in 1886.
 Set a Standard Jackson County Monument to replace the Fireclay and left Fireclay buried on the North side of the Monument and the pinched iron on the South side.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 T4S, R3W Corner is a 4" diameter X 36" concrete monument with a 1/2" X 36" steel rod and an aluminum cap stamped LS 18658, which is the standard monument for Jackson County.
 N 35° E 15" Oak 71.64' 40d & washer on Southwest side
 N 70° E 9" Oak 29.98' 40d & washer on North side
 S 70° E 15" Oak 54.34' 40d & washer on North side
 S 35° E 24" Oak 47.87' 40d & washer on Northeast side
 S 40° W 10" Maple 60.63' 40d & washer on West side
 N 80° W 3" Hickory 54.00' center line, no nail
 N 20° W 10" Maple 66.40' 40d & washer on Northeast side
 East Steel post and survey marker sign attached 30.0'



Signed by Dean R. Gutekunst Date November 30, 1996
 18658

Continued

M-13 T4S, R3W

A.) would be more in line with the closing distances is both T4S, R2W and T5S, R2W, as shown on the GLO maps) (DRG)

- Perpetuation by H. F. Bean, July 1886	Post standing with stones
W. Oak 24" S 36 E 141½ links (93.39')	around it. Found remains of
W. Oak 18" N 53 E 80 links (52.80')	witnesses.

- Not recorded in P. A. - 74