

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR. 5 W
26 N 5 W

Kalkaska COUNTY

DESCRIPTION OF CORNER Corner common to Sections 1, 2, 35, 36

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" B. Oak - S16W - 13 links

9" W. Oak - N64W - 20 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement by Forestry Division survey crew while making a partial resurvey of this township. No positive identification of original BTs. Used corners 1 mile east and 1 mile west for proportion.

Corner was placed and witnessed Dec. 21, 1956.

SURVEYORS SEAL

SIGNED *Billy D. Buckles*
REGISTERED LAND SURVEYOR

DATE 12/26/56