

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 25. NR. 5 W.  
26 NR 5 W

----- Kalkaska ----- COUNTY

DESCRIPTION OF CORNER Corner common to Sections 5, 6, 31, 32 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER -----

----- 12" B. Oak ----- S27W ----- 36 links  
5" J. Pine ----- N66W ----- 63½ links  
-----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measure by Forestry Division survey crew while making a partial resurvey of this township. Corners 1 mile west and 3 miles east were used in the proportion. No original evidence.

Corner was placed and witnessed Dec. 17, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 12/26/56