

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR 5 W.  
26 NR 5 W.

----- Kalkaska COUNTY

DESCRIPTION OF CORNER Corner common to Sections 4, 5, 32, 33 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER -----

7" B. Oak - S89W - 22½ links

5" Maple - N5W - 27½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measure by Forestry Division survey crew while making a partial resurvey of this township. No evidence of the original Bts. Corners 2 miles west and 2 miles east were used in the proportion.

SURVEYORS SEAL

SIGNED Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 12/26/56