

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR. 5 W.  
26 NR 5 W

----- Kalkaska ----- COUNTY

DESCRIPTION OF CORNER Corner common to Sections 3, 4, 33, 34 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER -----

5" B. Oak - S20E - 16 links -----

8" B. Oak S76W - 60 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measure by Forestry Division survey crew while making a partial resurvey of this township. Corners 3 miles west and 1 mile east were used in this proportion. No positive original evidence.

Corner was placed and witnessed Dec. 17, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 12/26/56