

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR. 5 W.
26 NR. 5 W

Kalkaska COUNTY

DESCRIPTION OF CORNER Corner common to Sections 2, 3, 34, 35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" W. Oak - N54W - 50½ links
6" B. Oak - N61E - 78 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by Forestry Division survey crew while making a partial resurvey of this township. Corner was established from possible SW original BT stump. Corner checks good for 6 mile proportion of entire town line, and with a good corner 1 mile north.

Corner was placed and witnessed Dec. 17, 1956

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 12/26/56
REGISTERED LAND SURVEYOR