

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:

| Kalkaska (County) | Located In | Corner Code # |
|---|-------------------------|---------------|
| 1. Public Land Survey | T _____ R _____ | _____ |
| 2. Property Controlling in Section | T _____ R _____ | _____ |
| | S 6 T 25N R 6W | 3 |
| | S 6 T 25N R 6W | 10 |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Dec 3, 1997 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|----|----|----|----|----|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

3 - Richards, Findroff, Richards - 1968 - Set Conc. Mon. 10 - None

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

| | |
|--|--|
| <p><u>3</u> - N 1/16, Sec. 6, T25N, R6W & Sec. 1, T25N, R7W - Fnd. 1/2" Iron in Conc. Mon. per Richards, Findroff, Richards - 1968 Survey at corner of new Deer fence N & E. Monument accepted as best available evidence of the position of the corner.</p> | <p><u>10</u> - S 1/16, Sec. 6, T25N, R6W & Sec. 1, T25N, R7W. Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure. 6.5' W of CL. N-S Gravel Drive. A 1/2" Rebar was fnd. N9°08'W 6.75' but was not accepted.</p> |
|--|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|--|--|
| <p><u>3</u> - Conc. Mon with 1/2" Iron Set Blue Carsonite Post 1' ± SW S80°E 0.70' to N&T in face 8" wood Anchor Post S70°E 49.27' to N&T in S. side 12" W. Pine West 26.92' to N&T in S. side 2" W. Pine N13°W 37.34' to N&T in E. Side 8" R. Maple</p> | <p><u>10</u> - 2" Alum. Cap on 5/8" x 34" Rebar - Down 0.5' East 33' to 2" Alum. Cap on 5/8" x 34" Rebar on S 1/16 line W 33' Blue Carsonite Post w/loc. Tag N64°W 119.31' to N&T in NE side 20" W. Pine S25°W 101.96' to N&T in E. side 25" W. Pine S37°E 57.69' to N&T in SW side 9" W. Pine</p> |
|--|--|

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 10/19/2000

