

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF --: | LOCATED IN --: | CORNER CODE NUMBER |
|---|---|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>25</u> N. <u>6</u> <u>W.</u> R. <u>6</u> <u>W.</u> | <u>E-4</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>8</u> | T. <u>25</u> N. <u>6</u> <u>W.</u> R. <u>6</u> <u>W.</u> | <u>6</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. _____ E. _____ S. _____ R. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 14, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-4 Fd. old pointed 4" dia. post bottom, old pointed stake bottom and Fargo (1912) butter dishes--all buried in muck; also fd. Fargo (1912) B.T."Tipped out W. Pine Stump 28", N55°E, 29'±". Fargo had both U.S. B.T.'s in 1912. We fd. Fargos 1" pipe ("L" end had been straightened out) shoved in ground 0.4' SE of Parker's buried 1/2" rod; Parker's 1/2" rod being N55°00"W, 11.8" from true Fargo position. We placed a DNR Mon. cap on 1" x 36" pipe inside of 1 1/4" x 48" pipe, all driven in muck & Sqd. Ced. Post--at Fargo's position.
- 6 Established ctr. of NE 1/4 of Sec. 8 per std. B.L.M. instructions based on our controlling corners of Sec. 8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| E-4 | 6 |
|--|--|
| Fd. Fargo Cor.-Set DNR Mon. & Ced Post. | Drove 5/8" x 36" rerod w/RLS cap & set |
| Set 5/8" x 36" rerod w/RLS cap & ced. post | cedar post w/loc tag. |
| N01°00'W 227.05' | 20" R. Pine S64°E 120.6' |
| Set 5/8" x 36" rerod w/RLS cap & Ced. post | 8" Cherry S78°W 86.2' |
| S89°37'E 29.00' | 12" Cherry S04°E 117.3' |
| Set 5/8" x 36" rerod w/RLS cap & ced. post | |
| S00°47'E 180.21' | |
| Set 5/8" x 36" rerod w/RLS cap & ced post | |
| N89°33'W 36.00' | |

SIGNED BY Carl F. Roser DATE 11-12-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

KALKASKA COUNTY