

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>8</u> , T. <u>25</u> , R. <u>6</u> _____	N. S., R. <u>6</u> _____ E. W.	<u>5, 2, 7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 14, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 5 Established SW corner of NW1/4 - NE1/4 of Sec. 8 mid-way & on line between our previously recorded N1/4 cor. & Ctr. of Sec. 8.
- 2 Established NE corner of NW1/4 - NE1/4 of Sec. 8 mid-way & on line between NE Cor. & N1/4 cor. of Sec- 8.
- 7 Established NE corner of S1/2 - NE1/4 of Sec. 8 mid-way and on line between previously recovered, witnessed and recorded NE of Sec. 8 and Fargo's (from USBT's) E1/4 of Sec. 8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5	2	7
Drove 5/8" x 36" rerod w/RLS cap & set ced. post w/loc tag.	Drove 5/8" x 36" rerod.	Drove 5/8" x 36" rerod w/RLS cap & set ced. post w/loc tag.
7" Maple (in cluster)	10" W. Pine S04°E 52.28	20" R. Pine N40°W 45.9'
N06°W 11.9	18" R. Pine S34°W 104.61	9" Cherry N74°E 14.7'
5" W. Oak N34°E 22.9	17" Cedar N60°W 67.22	10" Cherry S56°W 32.6'
4" R. Pine S44°W 22.7	Set ced. post w/loc tag South 33'	Fd 5/8" iron rod N33°56'W 9.42'
fd. 3/8" rerod N70°16'E 3.97	Ctr. gravel rd. N45°W 14'±	Ctr. E-W trail Rd. South 68'±
N. edge of Cannon Creek South 165'±	Approx. Ctr. of conc. box culv. N60°E 12'±	

SIGNED BY Carl F. Roser DATE 11-12-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ KALKASKA COUNTY