

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1998 REMONUMENTATION

1. Public Land Survey T 25N R 7W B-3  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

**FEB 22 1999**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6	5	4	3	2	1					
3		●										
4		7	8	9	10	11	12					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Eugene D. Farrier, in a field survey on October 30, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

**B-3, 1/4 Cor. Common to Secs. 6 & 7, T25N-R7W, Garfield Township**  
 1853, subdivision of Twp., by Deputy Surveyor T. Whelpley; set post; Beech 20", S 81 1/2 E, 38 Lk. (25.08') ; Birch 20", N38°E, 37 Lk. (24.42')  
 1900, Sec. 7 sub. survey by W.S. Merrill Co. Surveyor, Co. Survey Bk., Pg 28, found old cor. stone, no accessories  
 1903, Sec. 6 sub. survey by W.S. Merrill Co. Surveyor, Co. Survey Bk., Pg 26, found old cor. stone, no accessories  
 12-2-76, L. Drago, found iron, Liber 1, Pg. 943, Cert. of Survey  
 5-1-84, E. Farrier, found 1/2" iron in CL road on North-South fence, Cert. of Survey  
 6-4-90, N. DeYoung, found 1/2" rod, Cert of Survey  
 11-26-97, D. Grier, found 1/2" iron in CL Rd, Cert. of Survey  
 7-9-98, R. Kral, found 1/2" re-bar in CL road on North-South fence


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**B-3, 1/4 Cor. Common to Secs. 6 & 7, T25N-R7W, Garfield Township**  
 Found and accepted 1/2" iron in CL road on fence to North & 3.5' West of O.H.P. (as recorded in previous Cert. of Surveys) Pulled and set 5/8" X 18" re-bar w/brass cap.  
 No G.L.O. witnesses were found.  
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group  
 P.A. 345 - 1990 Kalkaska County  
 Chairman Eugene Farrier  
 Date 2-2-99

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**B-3, 1/4 Cor. Common to Secs. 6 & 7, T25N-R7W, Garfield Township**  
 Found and accepted 1/2" iron in CL road on fence to North & 3.5' West of O.H.P. Pulled and set 5/8" X 18" re-bar w/brass cap.  
 N28°W, 36.91' - 8" Ash, set nail & washer  
 N48°E, 27.13' - 6" Twin Maple, set nail & washer  
 S57°E, 31.24' - 6" Twin Maple, set nail & washer  
 S12°W, 47.50' - Power pole, set nail & washer



Signed by Eugene Farrier  
 Michigan License No. 24594

Date 2-8-99 Surveyor's



**3012643**  
 Page: 1 of 1  
 02/10/1999 08:27A  
 LB: 5 PG: 298

VEYORS, JAN. 28, 197  
 REVISED MAY 14, 197  
 REVISED JAN., 199  
 REVISED OCT., 199