

**SURVEY &  
REMONUMENTATION**

FEB 13 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA Located In: Corner Code #  
(County)  
1997 REMONUMENTATION  
1. Public Land Survey T 26N R 7W C-13  
T 25N R 7W C-1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_


I, EUGENE FARRIER, in a field survey on OCTOBER 24, 1997  
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
C-13: Cor. Common to Sec. 31 & 32, T26N-R7W Orange Twp. & Sec. 5 & 6, T25N-R7W, Garfield Twp.  
11-22-1900, County Surveyor, used cor., no accessories  
07-13-1984, N.B. DeYoung #20705, Cert. Survey, fd. Eye bolt, w/accessories, Lib 3, Pg. 3  
04-08-1988, Farrier Surveying, Cert. Survey, fd. Eye bolt, w/accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
C-13: Cor. Common to Sec. 31 & 32, T26N-R7W Orange Twp. & Sec. 5 & 6, T25N-R7W, Garfield Twp.  
Fd. 3/4" x 24" iron rod w/saddle on top, 5' West & 5' South of CL inter. Of 2-track trails. Pulled and replaced with 5/8" x 18" rebar, w/aluminum cap. No GLO witnesses were fd. The Kalkaska Co. Peer group approved and accepted the above monument as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-13: Cor. Common to Sec. 31 & 32, T26N-R7W Orange Twp. & Sec. 5 & 6, T25N-R7W, Garfield Twp.  
Fd. 3/4" x 24" iron rod w/saddle on top, 5' West & 5' South of CL inter. Of 2-track trails. Pulled and replaced with 5/8" x 18" rebar, w/aluminum cap.  
Fd. Nail N15W, 5" Tw. Maple, 22.10'  
Fd. Nail S80E, 9" Maple, 26.42'  
Fd. Nail South, 14" Beech, 23.50'  
Fd. Nail S85W, 12" Maple, 21.73'

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County  
Chairman Eugene Farrier  
Date 1-29-98

Signed by Eugene Farrier  
Michigan License No. 24594

Date 2-3-98 Surveyor's

**3004832**  
Page: 1 of 1  
02/04/98 11:22A