

MAR 01 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

KALKASKA Located In: Corner Code #
 (County)
 1999 REMONUMENTATION
 1. Public Land Survey T 25N R 7W C-9
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R



3020154
Page: 1 of 1
02/04/2000 03:40P
REMON
LB: 6 PG: 100

Kalkaska County Joan Hall, Register

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EUGENE FARRIER, in a field survey on November 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
C-9; Sec. Cor. Common to Sec. 19, 20, 29 & 30, T25N-R7W, Garfield Township
 1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co. Survey Notes Pg. 65, set post corner, Beech, 10", N61.5°W, 6 Lks; Hemlock 20", N10.25°W, 16 Lks; Hemlock 12", N33°E, 30 Lks
 1907, Survey, by W.S. Merrill (Co. Surveyor) Co. Survey Bk 23, Pgs 48-50, established proportional distance (no accessories)
 1912, Survey, by Fargo, found stake set by co. surveyor in center of road North, South, East & West, settler's say perp't. U.S corner accepted
 1973, LCRC, by J.F. Erickson, set railroad spike by double proportion distance, 5' East of centerline of N-S Road at centerline of E-W Road, N50°E, 54.97', telephone pole; S45°E, 49.00', power pole; S40°W, 62.73', fence post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-9; Sec. Cor. Common to Sec. 19, 20, 29 & 30, T25N-R7W, Garfield Township
 Found railroad spike 1.5' North of centerline of E-W road and 4' East of centerline of N-S road.
 N45°E, 44.28', corner fence post, set nail & washer
 S40°E, 49.10', power pole, set nail & washer
 S42°W, 64.42', 4" R. Pine, set nail & washer
 N40°W, 41.70', face of stop sign post; set nail & washer
 No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-9; Sec. Cor. Common to Sec. 19, 20, 29 & 30, T25N-R7W, Garfield Township
 Found railroad spike 1.5' North of centerline of E-W road and 4' East of centerline of N-S road. Pulled and set 5/8" X 18" rod w/ brass cap.
 N45°E, 44.28', corner fence post, set nail & washer
 S40°E, 49.10', power pole, set nail & washer
 S42°W, 64.42', 4" R. Pine, set nail & washer
 N40°W, 41.70', face of stop sign post; set nail & washer
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Signed by Eugene Farrier
 Michigan License No. 24594

Date 02-04-00 Surveyor's