

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA Located In: Corner Code #
 (County)
 1998 REMONUMENTATION
 1. Public Land Survey T 25N R 7W E-4
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

**SURVEY &
 REMONUMENTATION**

FEB 22 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on October 28, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-4: 1/4 Cor. Common to Secs. 8 & 9, T25N-R7W, Garfield Township
 1853, Subd of Twp., by Deputy Surveyor T. Whelpley; set post; Beech 4", N 89°E, 12 Lk. (7.92'); Sugar 12", N 35°W, 23 Lk. (15.18')
 1908, Sec. Sub. survey by W.S. Merrill CS, Co. Survey Bk. Pg. 45; notes found old cor. established by E. Mosher CS.
 12-8-89, E. Farrier, set r.r. spike 2.6' West of centerline of M-66 by single proportionate distance between section corners. LCRC, Liber 2, Pg. 393
 3-11-98, E. Farrier, found r.r. spike, 2.6' West of centerline of M-66, Cert. of Survey

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 2-2-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4: 1/4 Cor. Common to Secs. 8 & 9, T25N-R7W, Garfield Township
 Found and accepted r.r. spike, 2.6' West of centerline of M-66 (as recorded in LCRC) Pulled & set 5/8" X 18" re-rod w/brass cap in mon. box
 S55°E, 108.40' - Power pole, set nail & washer
 S83°W, 49.12' - 20" Maple, set nail & washer
 No G.L.O. witnesses were found.
 Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4: 1/4 Cor. Common to Secs. 8 & 9, T25N-R7W, Garfield Township
 Found and accepted r.r. spike, 2.6' West of centerline of M-66
 N50°E, 77.74' - 8" Cherry, set nail & washer
 N85°E, 69.80' - 10" Cherry, set nail & washer
 S55°E, 108.40' - Power pole, set nail & washer
 S83°W, 49.12' - 20" Maple, set nail & washer
 N86°W, 32.95' - Iron & cap # 28432 & 31611



Signed by Eugene Farrier
 Michigan License No. 24594

Date 2-8-99 Surveyor's

3012653
 Page: 1 of 1
 02/10/1999 08:30A
 Kalkaska County REMON 9.00 LB: 5 PG: 308

L SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1993
 REVISED OCT., 1996