

RECORDED & INDEXED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DATE: 02-04-2000

For corners in

KALKASKA

(County)

Located In:

Corner Code #

SECTION:

1999 REMONUMENTATION

1. Public Land Survey

T 25N R 7W

E-6

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___



3020157
Page: 1 of 1
02/04/2000 03:40P
REMON
LB: 6 PG: 103

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on November 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		11		12		13		14		15		16
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6: 1/4 Cor. Common to Sec. 16 & 17, T25N-R7W, Garfield Township

1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co. Survey Notes Pg 50, set 1/4 Section post, Birch 12", S60°E, 25 Lks; Hemlock 10", N32°W, 23 Lks

1905, Survey, by W.S. Merrill (Co. Surveyor) Co Survey Bk 22, Pg 44-46, found stump of bearing tree, no accessories

1914, Survey, by W.S. Merrill (Co. Surveyor) Co Survey Bk 34, Pg 87-88, iron, no accessories

1975, Survey, by J.L. Fletcher, recorded in Liber 1, Pg 723-729, found 1/2" rod in mon. box, nail in corner fence S89°E, 77.65'; found nail in power pole, N66°W, 78.93'; + in 373 + 10 t/h wall, S14°W, 185.55'

1973, Survey, by J.F. Erickson, recorded in Liber 1, Pg 334, no accessories

1976, Survey, by J.L. Fletcher, recorded in Liber 1, Pg 834 & Liber 1, Pg 926 & Liber 2, Pg 260, 1/2" rod in mon. box corner fence post, S89°E, 77.65'; power pole, N66°W, 78.93', + in 373 + 10 on conc.; head wall S14°W, 185.55'

1999, Survey, by Farrier Surveying, found 1/2" iron in mon. box in c/l Highway M-66 & on old fence to East, set nail N58°E, 8" R. Pine, 87.08', set nail East 7", Twin Cherry, 65.10'; set nail S65°E, 5" Cherry, 91.48'; N70°W, power pole, 78.97'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6: 1/4 Cor. Common to Sec. 16 & 17, T25N-R7W, Garfield Township

Found 1/2" iron in mon. box 0.5' West of centerline M-66 & on fence to East.

N58°E, 87.08', 8" R. Pine, found nail

East, 65.10', 7" Twin Cherry, found nail

S65°E, 91.48', 5" Cherry, found nail


N70°W, 78.47', power pole, found nail

No G.L.O. witnesses were found.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman [Signature]

Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6: 1/4 Cor. Common to Sec. 16 & 17, T25N-R7W, Garfield Township

Found 1/2" iron in mon. box 0.5' West of centerline M-66 & on fence to East. Added brass cap.

N58°E, 87.08', 8" R. Pine, found nail

East, 65.10', 7" Twin Cherry, found nail

S65°E, 91.48', 5" Cherry, found nail

N70°W, 78.47', power pole, found nail

Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Signed by [Signature]
Michigan License No. 24594

Date 02-04-00 Surveyor's