

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA
 (County)

Located In:

Corner Code #

1999 REMONUMENTATION
 1. Public Land Survey

T 25N R 7W E-7

2. Property Controlling
 in Section

S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____
 S _____ T _____ R _____

RE SURVEY &
 REGISTERED

MAR 1 2000

SECTION



3020158

Page: 1 of 1
 02/04/2000 03:46P
 REMON
 LB: 6 PG: 104

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on November 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-7: Sec. Cor. Common to Sec. 16, 17, 20 & 21, T25N-R7W, Garfield Township
 1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co. Survey Notes Pg 20, set post corner, Black Ash 16", N4°E, 20 Lks; Cedar 20", N45.75°W, 34 Lks; Hemlock 14", S39°E, 60 Lks;
 1907, Survey, by W.S. Merrill (Co. Surveyor) Co. Survey Bk 34, Pg 87 & 88, Cedar stump 18", S88°W, 45 Lks
 1914, Survey, by W.S. Merrill (Co. Surveyor) Co. Survey Bk 22, Pgs 44-46, old corner iron pipe, no accessories
 1912, Fargo Survey, found old stake and remains of 3 US witnesses
 1975, Survey, by J.F. Erickson, recorded in Liber 1, Pg 334, no accessories
 1975; 1976; 1980, Survey & LCRC, by J.L. Fletcher, (1976 Survey recorded in Liber 1, Pg 834; 1980 LCRC recorded in Liber 2, Pg 200), found bolt spike, 20.9' West of centerline M-66, nail in guard rail post, S47°E, 63.28'; nail in guard rail post, N40°E, 56.18'; center top row marker, N89°W, vertical angle 77°34'50" slope dist. 81.73'
 1980, Survey, by E. Farrier (Co. Surveyor) found iron in mon box, same wit. as Fletcher (1980)
 1983, Survey, by E. Farrier (Co. Surveyor) found boat spike 20.5' West of centerline M66, S40°E, 56.60', nail in top of guard rail post; N47°E, 54.30', nail in top of guard rail post; S85°E, 40.70'; West 79.50', 1/2" rod on Section line and right-of-way
 1985, Survey, by N.B.DeYoung, recorded in Liber 3, Pg 237, no accessories
 1998, Survey, by Farrier Surveying, found bolt spike, 20.3' West of centerline Highway M-66, set nail N40°E, T/wood guard rail post, 63.48', set nail S47°E, wood guard rail post, 58.84'; set nail S50°W, 12" W. Pine 103.23'; West found iron & cap #19830, 79.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7: Sec. Cor. Common to Sec. 16, 17, 20 & 21, T25N-R7W, Garfield Township
 Found boat spike 20.3' West of centerline of M-66.
 N40°E, 63.48', T wood guard rail post, found nail
 S47°E, 58.84', T wood guard rail post, found nail
 S50°W, 103.23', 12" W. Pine, found nail
 West, 79.40', iron & cap #19830
 No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman [Signature]
 Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7: Sec. Cor. Common to Sec. 16, 17, 20 & 21, T25N-R7W, Garfield Township
 Found boat spike 20.3' West of centerline of M-66. Pulled & set 5/8" X 18" rerod w/aluminum cap.
 N40°E, 63.48', T wood guard rail post, found nail
 S47°E, 58.84', T wood guard rail post, found nail
 S50°W, 103.23', 12" W. Pine, found nail
 West, 79.40', iron & cap #19830
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Signed by [Signature]
 Michigan License No. 24594

Date 02-04-00 Surveyor's