

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

SURVEY &  
 RECORDATION

MAR 11 2000

For corners in

KALKASKA  
 (County)

Located in:

Corner Code #

SECTION

1999 REMONUMENTATION

1. Public Land Survey

T 25N R 7W E-9

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_



Kalkaska County Joan Hall, Register

**3020160**

Page: 1 of 1

02/04/2000 03:40P

REMON

LB: 6 PG: 106

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on November 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-9: Sec. Cor. Common to Sec. 20, 21, 28, & 29, T25N-R7W, Garfield Township

- 1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor), Co. Survey Notes Pg 59, set post corner, Hemlock 12", N23.25°E, 3 Lks; Hemlock 20", S63.25°E, 17 Lks; Cedar 8", S23.5°W, 28 Lks
- 1912, Fargo Survey, found old stake in center of road E & W, Cedar stump 10", S35°W, 0.57 1/2 Ch; W. Pine, 8", N44.5°E, 1.33 1/4 Ch.
- 1973, Survey & LCRC, by J.F. Erickson, (Survey recorded in Liber 1, Pg. 285; LCRC recorded in Liber 1, Pg. 196) found 3/4" pipe in mon box 7' West of centerline of M-66 and 3' North of centerline of Lund Road; N60°E, power pole, 75.39'; N60°W, phone pole, 80.37'; S70°E, 14" Pine, 109.75'
- 1974, Survey, & LCRC, by J.L. Wilcox, (Survey recorded in Liber 1, Pg. 615; LCRC recorded in Liber 1, Pg. 341), same as Erickson (1973)
- 1978, Survey, by N. Parker, (recorded in Liber 2, Pg. 282) found same as Erickson (1973)
- 1985;1987;1988, Survey, by E. Farrier (Co. Surveyor) found same as Erickson (1973)
- 1995, Survey, by Farrier Surveying, found same as Erickson (1973)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9: Sec. Cor. Common to Sec. 20, 21, 28, & 29, T25N-R7W, Garfield Township

- Found 3/4" iron pipe in mon box 7.0' West of centerline of M-66 & 4.5' North of centerline of Lund Road.
- N60°E, 75.36', power pole, found nail & tag
- S70°E, 158.64, NW cor. old motel
- S72°W, 106.38', power pole, set nail & washer
- N42°W, 99.42', 14" W. Birch, set nail & washer
- No G.L.O. witnesses were found.

Ratified by Peer Group  
 P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9: Sec. Cor. Common to Sec. 20, 21, 28, & 29, T25N-R7W, Garfield Township

- Found 3/4" iron pipe in mon box 7.0' West of centerline of M-66 & 4.5' North of centerline of Lund Road. Added 5/8" X 18" re-rod w/ aluminum cap.
- N60°E, 75.36', power pole, found nail & tag
- S70°E, 158.64, NW cor. old motel
- S72°W, 106.38', power pole, set nail & washer
- N42°W, 99.42', 14" W. Birch, set nail & washer
- Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Signed by Eugene Farrier  
 Michigan License No. 24594

Date 02-04-00 Surveyor's