

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
 REGISTERED
 MAR 01 2000

For corners in

KALKASKA
 (County)

Located In: Corner Code #

1999 REMONUMENTATION

1. Public Land Survey

T 25N R 7W F-1
 T 26N R 7W F-13

SECTION

2. Property Controlling
 in Section

S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____
 S _____ T _____ R _____

3020151
 Page: 1 of 1
 02/04/2000 03:40P
 REMON
 LB: 8 PG: 107



Kalkaska County Joan Hall, Register

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

I, EUGENE FARRIER, in a field survey on November 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1: 1/4 Cor. Common to Sec. 4, T25N-R7W, Garfield Township; F-13: Sec. 33, T26N-R7W, Orange Township

1853, G.L.O. Resurvey, V.W. Caukin (Deputy Surveyor) Co. Survey Notes, Pg. 13, set 1/4 Sec. post, Beech 9", N2°E, 5 Lks; Beech 12", N32°W, 34 Lks
 1903, Survey, by W.S. Merrill (Co. Surveyor) Co Survey Bk 25, Pgs. 2 & 3, found one B.T., Maple 14", S38°E, 28.5 Lks
 1986, Survey, by E. Farrier (Co. Surveyor), set 1/4" X 39" iron pipe by fence line occupation.
 1997, Survey, by Farrier Surveying, found 1/4" iron pipe cap #24594 on fence line to E, N & S, N49°E, 66.43', 10" W. Pine, N14°W, 53.34', 7" R. Pine; N54°W, 85.73', 10" R. Pine, South 9.70', 6" Cherry, fence to West is 31.5' North of corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1: 1/4 Cor. Common to Sec. 4, T25N-R7W, Garfield Township; F-13: Sec. 33, T26N-R7W, Orange Township

Found 1/4" X 39" iron pipe w/ cap #24594, 31.5' S. of old fence to W., & on tree line to S. & on old fence to N. & E.
 N59°W, 85.71', 12" R. Pine, set nail & washer
 N19°W, 53.30', 10" R. Pine, set nail & washer
 N45°E, 66.41', 16" W. Pine, set nail & washer
 South, 9.67', 10" Cherry, set nail & washer
 No G.L.O. witnesses were found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1: 1/4 Cor. Common to Sec. 4, T25N-R7W, Garfield Township; F-13: Sec. 33, T26N-R7W, Orange Township

Found 1/4" X 39" iron pipe w/ cap #24594, 31.5' S. of old fence to W., & on tree line to S. & on old fence to N. & E. Added aluminum cap.
 N59°W, 85.71', 12" R. Pine, set nail & washer
 N19°W, 53.30', 10" R. Pine, set nail & washer
 N45°E, 66.41', 16" W. Pine, set nail & washer
 South, 9.67', 10" Cherry, set nail & washer
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 02-03-00

Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 02-04-00