

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED &
INDEXED

MAR 12 2000

SECTION

For corners in

KALKASKA
 (County)

Located in:

Corner Code #

1999 REMONUMENTATION

1. Public Land Survey

T 25N R 7W

G-4

T R

T R

T R

2. Property Controlling
 in Section

S

T R

S

T R

3. Miscellaneous
 Property in Sec.

S

T R

S

T R



Kalkaska County Joan Hall, Register

3020169

Page: 1 of 1
 02/04/2000 03:40P
 REMON
 LB: B PG: 115

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9	●	10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, EUGENE FARRIER, in a field survey on November 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4; 1/4 Cor. Common to Sec. 9 & 10, T25N-R7W, Garfield Township

1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co Survey Notes Pg 45, set 1/4 Section post, Beech 12", N32.25°W, 42 Lks; Beech 10", S28.25°E, 33 Lks
 1901; 1904, Survey, by W.S. Merrill (Co. Surveyor) Co. Survey Bk 11, Pg 84-85, & Bk 25, Pg. 132, no acc.
 1989, 1990, 1998, LCRC & Survey, by E. Farrier (Co. Surveyor) found 1" iron pipe with a 3/8" rod riser in e/l N-S road, found nail in power pole, N44°W, 38.86', nail in 10" Apple, S61°W, 94.65'; nail in 8" R. Pine, S23°E, 68.52'; nail in 6" Apple, S72°E, 54.61'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4; 1/4 Cor. Common to Sec. 9 & 10, T25N-R7W, Garfield Township

Found 3/8" X 18" rerod raised over 1" iron pipe in centerline N-S road. Pulled 3/8" rerod and replaced with 5/8" X 18" rerod w/brass cap.
 N65°E, 49.16', 3" R. Pine, set nail & washer
 S27°E, 68.51', 10" R. Pine, set nail & washer
 S20°W, 91.08', 3" X 3" sq. wood post, set nail & washer
 N50°W, 38.84', power pole, set nail & washer over old nail
 No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 02-03-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4; 1/4 Cor. Common to Sec. 9 & 10, T25N-R7W, Garfield Township

Found 3/8" X 18" rerod raised over 1" iron pipe in centerline N-S road. Pulled 3/8" rerod and replaced with 5/8" X 18" rerod w/brass cap.
 N65°E, 49.16', 3" R. Pine, set nail & washer
 S27°E, 68.51', 10" R. Pine, set nail & washer
 S20°W, 91.08', 3" X 3" sq. wood post, set nail & washer
 N50°W, 38.84', power pole, set nail & washer over old nail
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.



Signed by Eugene Farrier
 Michigan License No. 24594

Date 02-04-00

Surveyor's