

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA

Located In:

Corner Code #

(County)

1999 REMONUMENTATION

1. Public Land Survey

T 25N R 7W

G-5

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

MAY 14 2000

SECTION



**3020170**

Page: 1 of 1  
02/04/2000 03:40P  
REMON  
LB: 6 PG: 116

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on November 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-5: Sec. Cor. Common to Sec. 9, 10, 15, & 16, T25N-R7W, Garfield Township

1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co Survey Notes Pg. 45, set post corner, Beech 5", N12°W, 29 Lks; Beech 10", N14°E, 40 Lks; Beech 15" S69°E, 37 Lks

1900;1904;1905, Survey, by W.S. Merrill (Co. Surveyor) Co. Survey Bk 11, Pgs 84-85; 1904- Bk 25, Pg 132-133; 1905- Bk 22, Pgs 44-46, no acc.

1979, Survey, by G. Fauser for Consumers Power Co., recorded in Liber 2, Pg. 316, found square iron bar

1981, LCRC & Survey, by E. Farrier (Co. Surveyor), recorded in Liber 2, Pg. 303, found 1/2" rod in centerline of roads

1998, Survey, by Farrier Surveying, found 1/2" rod in centerline of roads

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5: Sec. Cor. Common to Sec. 9, 10, 15, & 16, T25N-R7W, Garfield Township

Found and accepted 1/2" X 6" iron & cap #24594, raised over 1/2" iron in centerline 4-way road int. N45°E, 36.22', cor. fence post, set nail & washer


S57°E, 51.30', 28" Maple, found nail

S50°W, 59.90', power pole, found nail

N30°W, 65.46' 28" Maple, found spike

N35°W, 25.93', 1" iron pipe, set GFA

No G.L.O. witnesses were found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5: Sec. Cor. Common to Sec. 9, 10, 15, & 16, T25N-R7W, Garfield Township

Found and accepted 1/2" X 6" iron & cap #24594, raised over 1/2" iron in centerline 4-way road int. Pulled & set 5/8" X 18" rerod with brass cap.

N45°E, 36.22', cor. fence post, set nail & washer

S57°E, 51.30', 28" Maple, found nail

S50°W, 59.90', power pole, found nail

N30°W, 65.46' 28" Maple, found spike

N35°W, 25.93', 1" iron pipe, set GFA

Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 02-03-00

Signed by Eugene Farrier  
Michigan License No. 24594

Date 02-04-00 Surveyor's