

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED
 MAR 11 2000

For corners in

KALKASKA Located In: Corner Code #
 (County)
 1999 REMONUMENTATION
 1. Public Land Survey T 25N R 7W G-9
 T ___ R ___
 T ___ R ___
 T ___ R ___
 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

SECTION

3020174
 Page: 1 of 1
 02/04/2000 03:40P
 REMON
 LB: 8 PG: 120



4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on November 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-9: Sec. Cor. Common to Sec. 21, 22, 27, & 28, T25N-R7W, Garfield Township
 1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co. Survey Notes Pg. 41, set post, Beech 8", S9.5°E, 18 Lks (11.88"); Hemlock 10", S43.75°W, 29 Lks (19.14"); Y. Birch 8", N16°W, 12 Lks (7.92')
 1912, Survey, Fargo, found one U.S. witness, Hemlock stump N55°E, 0.755 Ch. (49.83"); Hemlock stump 24" N57.5°W, 107.5 Lks (70.95')
 1933, H.L. Botsford, found 3/4" pipe & crockery, L.E.S. cor. post N40°E, 40.4'; W.P. stump, S88°W, 62.2'; set railroad rail 33' East of corner
 1981, LCRC, by E. Farrier (Co. Surveyor), recorded in Liber 2, Pg. 305, found 3/4" iron pipe that fit 1933 survey made by Cons. Power, N06°E, 31.55', 2" Pipe (bad corner); N15°E, 82.75', power pole; East, 55.10', 20" Maple; S80°W, 22.22', 8" R. Pine, N34°W, 28.30', 7" Cherry
 1982, Consumers Power, D. Ankrom, found Fargo iron & crockery, 2 1/2" pipe, N2°E, 31.6'; 6" Red Pine, S85°W, 22.22'; 12" Maple, N75°E, 55.12'; 6" W. Cherry, N25°W, 28.33'
 1984, Survey, by E. Farrier (Co. Surveyor), found 1/2" Iron & Cap # 21265, set by D. Ankrom for Cons. Power Co. (1982)
 1988, Survey, by C.L. Robinson, recorded in Liber 3, Pg. 296, found 1/2" iron pipe; 2" iron pipe, N04°E, 30.82'; 15" Maple, N89°E, 55.18'; 9" R. Pine, N17°E, 59.98'; 6" R. Pine, S81°W, 22.24'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9: Sec. Cor. Common to Sec. 21, 22, 27, & 28, T25N-R7W, Garfield Township
 Found & accepted 3/4" iron pipe w/ broken crockery 1.5' West of centerline N-S seasonal road 82' +/- S. of OHP.
 N15°E, 82.75', power pole, found spike
 East, 55.20', 20" Maple, found spike
 S50°E, 23.86', 12" Cherry, set nail & washer
 S75°W, 22.00', 12" R. Pine, set nail & washer
 N06°E, 31.55', 2" pipe unaccepted for corner
 No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9: Sec. Cor. Common to Sec. 21, 22, 27, & 28, T25N-R7W, Garfield Township
 Found & accepted 3/4" iron pipe w/ broken crockery 1.5' West of centerline N-S seasonal road 82' +/- S. of OHP. Added 5/8" X 18" rod w/ brass cap.
 N15°E, 82.75', power pole, found spike
 East, 55.20', 20" Maple, found spike
 S50°E, 23.86', 12" Cherry, set nail & washer
 S75°W, 22.00', 12" R. Pine, set nail & washer
 N06°E, 31.55', 2" pipe unaccepted for corner
 Kalkaska County Peer Group accepted the above monument as a careful and faithful perpetuation of the position of the original corner.

Signed by Eugene Farrier
 Michigan License No. 24594

Date 02-04-00 Surveyor's