

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA
(County)

Located In:

Corner Code #

1999 REMONUMENTATION
 1. Public Land Survey

T 25N R 7W

H-1
H-13

T 26N R 7W

T _____ R _____

T _____ R _____

2. Property Controlling
 in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

RECORDED &
 INDEXED
 MAR 13 2000
 SECTION



3020175
 Page: 1 of 1
 02/04/2000 03:40P
 REMON
 LB: 6 PG: 121

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EUGENE FARRIER, in a field survey on November 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4			3		2		1
3													
4	7		8			9			10		11		12
5													
6	18		17			16			15		14		13
7													
8	19		20			21			22		23		24
9													
10	30		29			28			27		26		25
11													
12	31		32			33			34		35		36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1: 1/4 Cor. Common to Sec. 3, T25N-R7W, Garfield Twp; H-13: Sec. 34, T26N-R7W, Orange Twp.

1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co. Survey Notes, Pg 13, Sugar 24", 1/4 Sec. cor.
 1992, Survey, by E. Farrier (Co. Surveyor), set iron & cap #24594 in center road; S65°W, 58.94', power pole, S30°W, 60.73', 14" Twin Maple; N15°W, 34.00', fence post; N55°E, 53.34', service pole, set MPOL
 1993, Survey, by E. Farrier (Co. Surveyor), found 1/2" iron & cap, wit. same as 1992

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1: 1/4 Cor. Common to Sec. 3, T25N-R7W, Garfield Twp; H-13: Sec. 34, T26N-R7W, Orange Twp.

Found 1/2" X 18" iron & cap #24594 in centerline of E-W road, 11' East of fence to North & 27' East of fence to South, S65°W, 58.94', power pole, found nail
 N15°W, 34.00', corner fence post, found nail
 N55°E, 53.34', service pole, found nail
 S30°W, 60.73', 18" Twin Maple, found nail
 No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1: 1/4 Cor. Common to Sec. 3, T25N-R7W, Garfield Twp; H-13: Sec. 34, T26N-R7W, Orange Twp.

Found 1/2" X 18" iron & cap #24594 in centerline of E-W road, 11' East of fence to North & 27' East of fence to South. Pulled & replaced with 5/8" X 18" rerod w/ brass cap.
 S65°W, 58.94', power pole, found nail
 N15°W, 34.00', corner fence post, found nail
 N55°E, 53.34', service pole, found nail
 S30°W, 60.73', 18" Twin Maple, found nail

Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 02-04-00