

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

SURVEY &  
 RECORDS  
 DATE: 02 2000

For corners in

KALKASKA  
 (County)

Located In:

Corner Code #

SECTION

1999 REMONUMENTATION  
 1. Public Land Survey

T 25N R 7W H-5

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
 in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
 Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_



Kalkaska County Joan Hall, Register

**3020177**  
 Page: 1 of 1  
 02/04/2000 03:40P  
 REMON  
 LB: 6 PG: 123

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EUGENE FARRIER, in a field survey on November 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
H-5: 1/4 Cor. Common to Sec. 10 & 15, T25N-R7W, Garfield Twp

1853, G.L.O. Resurvey, by V.W. Caukin (Deputy Surveyor) Co. Survey Notes, Pg 48, set quarter sec. post, Beech 24", N68°E, 8 Lks; Beech 10", S36.25°E, 37 Lks  
 1904, Survey, by W.S. Merrill (Co. Surveyor) Co. Survey Bk 11, Pg 84 & 85 and Bk 25, Pg 132 & 133, Cedar stake, no witnesses  
 1981, LCRC, by E. Farrier (Co. Surveyor), recorded in Liber 2, Pg. 303, set 5/8" rod & cap #24594, 3' East of fence corner South, 12' East centerline of road, & in centerline of road West, 31' North of South r.o.w. & 29' West of East r.o.w. retraced survey of record along West 1/2 of North mile, fd NW & N 1/8 & doubled over to set H-5, N70°W, 76.55', 14" Maple; N55°E, 36.60' anchor pole; S45°E, 41.50', 16" Maple; S06°W, 49.37', 13" Maple  
 1984, Survey, by E. Farrier (Co. Surveyor), found 1/2" iron & cap #24594  
 1998, Survey, by Farrier Surveying, found 1/2" iron & cap #24594

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5: 1/4 Cor. Common to Sec. 10 & 15, T25N-R7W, Garfield Twp  
 Found 5/8" iron & cap #24594 3' East of fence to South 12' East of centerline road to North & in centerline road to West. Also 31' North of r.o.w. fence & 29' West of East r.o.w. fence.  
 N17°E, 67.29', 30" Maple, found nail  
 S49°E, 41.48', 16" Maple, found nail  
 South, 33.0', iron & cap #24594  
 N75°W, 76.48', 14" Maple, found nail  
 No G.L.O. witnesses were found.

Ratified by Peer Group  
 P.A. 345 - 1990 Kalkaska County  
 Chairman Eugene Farrier  
 Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5: 1/4 Cor. Common to Sec. 10 & 15, T25N-R7W, Garfield Twp  
 Found 5/8" iron & cap #24594 3' East of fence to South 12' East of centerline road to North & in centerline road to West. Also 31' North of r.o.w. fence & 29' West of East r.o.w. fence. Added brass cap.  
 N17°E, 67.29', 30" Maple, found nail  
 S49°E, 41.48', 16" Maple, found nail  
 South, 33.0', iron & cap #24594  
 N75°W, 76.48', 14" Maple, found nail  
 Kalkaska County Peer Group accepted the above monument as a careful and faithful reestablishment of the position of the original corner.

Signed by Eugene Farrier  
 Surveyor's Michigan License No. 24594

Date 02-04-00