

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COUNTY &
 RANGE
 SECTION

For corners in

KALKASKA Located In: Corner Code #
 (County)
 1999 REMONUMENTATION
 1. Public Land Survey T 25N R 7W 1-2
 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____



3020179
 Page: 1 of 1
 02/04/2000 03:40P
 REMON
 LB: 6 PG: 125

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3	●	2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on November 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
I-2: 1/4 Cor. Common to Secs. 2 & 3, T25N-R7W, Garfield Twp
 1853, G.L.O. Resurvey, V.W. Caukin (Deputy Surveyor) Co. Survey Notes, Pg 36, set quarter section post, Beech 3", N42.25°E, 16 Lks; Beech 8", S38.25°W, 21 Lks
 1901, Survey, by W.S. Merrill (Co. Surveyor) Co. Survey Bk 11, Pg 90 & 91, visited corner, no accessories
 1992, Survey, by E. Farrier (Co. Surveyor), found 5/8" rerod, power pole, S35°W, 83.95'; 14" Maple, S20°E, 103.09'; 5/8" rerod East 33.00'; 28" Maple, N30°E, 67.57'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-2: 1/4 Cor. Common to Secs. 2 & 3, T25N-R7W, Garfield Twp
 Found 5/8" rerod 4' West of centerline of N-S road on fence to West, and 22' +/- North of East-West Shell pipeline.
 N25°E, 67.57', 28" Maple, found nail
 S70°E, 54.08', 5" R. Pine, set nail & washer
 S29°E, 103.09, 14" Maple, found nail
 S28°W, 83.95', power pole, found spike
 No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-2: 1/4 Cor. Common to Secs. 2 & 3, T25N-R7W, Garfield Twp
 Found 5/8" rerod 4' West of centerline of N-S road on fence to West, and 22' +/- North of East-West Shell pipeline. Added brass cap.
 N25°E, 67.57', 28" Maple, found nail
 S70°E, 54.08', 5" R. Pine, set nail & washer
 S29°E, 103.09, 14" Maple, found nail
 S28°W, 83.95', power pole, found spike
 Kalkaska County Peer Group accepted the above monument as the best available evidence of the position of the original corner.

Signed by Eugene Farrier Date 02-04-00
 Surveyor's Michigan License No. 24594