

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA
 (County)

Located In:

Corner Code #

1999 REMONUMENTATION
 1. Public Land Survey

T 25N R 7W J-5

2. Property Controlling
 in Section

S T R

3. Miscellaneous
 Property in Sec.

S T R
 S T R



3020185
 Page: 1 of 1
 02/04/2000 03:40P
 REMON
 LB: 6 PG: 131

SECTION

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 13 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, EUGENE FARRIER, in a field survey on November 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-5: 1/4 Cor. Common to Secs. 11 & 14, T25N-R7W, Garfield Twp
 1853, G.L.O. Resurvey, V.W. Caukin (Deputy Surveyor) Co. Survey Notes, Pg 38, set quarter section post, Beech 5", N78.75°E, 8 Lks; Beech 10", S23.5°W, 31 Lks
 1903, Survey, by W.S. Merrill (Co. Surveyor) Co. Survey Bk 25, Pgs 20 & 21, visited corner, no accessories
 1912, Fargo Survey, found one U.S. witness, Beech 10" (now 13"), S23.5°W, 0.31 Ch.
 1980, Consumers Power Co, found 1" galvanized pipe at fence N-S and E
 1990, Survey & LCRC, by B. Jones, survey recorded in Liber 3, Pg. 363, found 1" pipe, S22°W, cluster Basswood, 40.6'; S75°W, 18" Twin Maple, 54.30'; N70°W, 15" Maple, 65.0'; N16°E, 10" Maple, 17.30'
 1999, Survey by E. Farrier (Co. Surveyor), found 1 1/4" galvanized iron pipe 5' +/- high at fence corner, fits Consumers power wits'; pulled and set 5/8" rod #24594, fences N-S & E-W, N10°E, 17.12', 6" Maple, S20°W, 40.60', 18" Twin Ash; S15°E, 13.96', 8" X 16" twin Elm, found nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-5: 1/4 Cor. Common to Secs. 11 & 14, T25N-R7W, Garfield Twp
 Found 5/8" rod (set 9-8-99) at fence intersection N-S, E-W.
 N10°E, 17.12', 6" Maple, found nail
 S20°W, 40.60', 18" Twin Ash, found nail
 S85°W, 51.42', 12" Maple, found nail
 S15°E, 13.95', 8" & 16" Twin Elm, found nail
 No G.L.O. witnesses were found.

Ratified by Peer Group
 P.A. 345 - 1990 Kalkaska County
 Chairman Eugene Farrier
 Date 02-03-00



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-5: 1/4 Cor. Common to Secs. 11 & 14, T25N-R7W, Garfield Twp
 Found 5/8" rod (set 9-8-99) at fence intersection N-S, E-W. Added aluminum cap.
 N10°E, 17.12', 6" Maple, found nail
 S20°W, 40.60', 18" Twin Ash, found nail
 S85°W, 51.42', 12" Maple, found nail
 S15°E, 13.95', 8" & 16" Twin Elm, found nail
 Kalkaska County Peer Group accepted the above monument as a careful and faithful perpetuation of the position of the original corner.

Signed by Eugene Farrier
 Surveyor's Michigan License No. 24594

Date 02-04-00