

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>24</u> T <u>25N</u> R <u>7W</u> S <u>24</u> T <u>25N</u> R <u>7W</u>	11 CSSW 1/64
3. Miscellaneous Property in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No: _____	Recorded Plat: _____	
5. Private Claims: _____		

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on March 15, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
11 - None CSSW 1/64 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
11 - SW 1/16 Cor. Sec. 24 - Set 2" Alum. Cap on 5/8" x 34" iron rebar per standard BLM procedure. CSSW 1/64 - being the SW Cor. of the N 1/2 of SE 1/4 of SW 1/4, Sec. 24 - Set 2" Alum. Cap on 5/8" x 34" iron rebar Per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
11 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar
 Set blue carsonite post w/ loc tag 1' NE
 West 11.48' to set N & T in S. side 10" R. Maple
 N20°W 12.63' to set N & T in SW side 6" Cedar
 S54°E 4.59' to set N & T in NE side 12" R. Maple
 S11°E 11.13' to set N & T in E. side Tw. 12" Cedar
 N48°E 24.28' to set N & T in side 8" Cedar
CSSW 1/64 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar
 Set blue carsonite post w/ loc tag 1' SE
 S36°W 9.99' to set N & T in NW side 22" R. Pine
 N86°E 19.42' to set N & T in N. side 6" R. Pine
 N22°E 10.14' to set N & T in W. side 19" R. Pine
 N42°W 9.05' to set N & T in SW side 9" R. Pine

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 8/3/2004