

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

|  |                                      |               |         |
|--|--------------------------------------|---------------|---------|
| For Corners In:<br><u>Kalkaska</u><br>(County) | Located In                           | Corner Code # |         |
| 1. Public Land Survey                          | T _____ R _____                      |               |         |
|  | T _____ R _____                      |               |         |
| 2. Property Controlling in Section             | S <u>25</u> T <u>25N</u> R <u>7W</u> |               | NN 1/64 |
|  | S <u>30</u> T <u>25N</u> R <u>6W</u> |               | NN 1/64 |
| 3. Miscellaneous Property in Section           | S _____ T _____ R _____              |               |         |
|  | S _____ T _____ R _____              |               |         |
| 4. Lot No: _____                               | Recorded Plat: _____                 |               |         |
| 5. Private Claims: _____                       |                                      |               |         |

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on April 20, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

|    |    |    |    |    |    |    |   |   |   |   |   |   |   |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

A. Description of original monument and accessories and/or subsequent restoration:  
NN 1/64 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
NN 1/64 - corner common to Sec. 25, T25N, R7W and Sec. 30, T25N, R6W, - being the NE corner of the S 1/2 of NE 1/4 of NE 1/4 of Sec. 30 - Set 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
NN 1/64 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar

- Set blue carsonite post w/ loc tag 1' SE
- N45°W 33.13' to set N & T in NE side 6" R. Pine
- S83°W 33.38' to set N & T in S side 4" W. Pine
- S25°W 36.63' to set N & T in NW side 8" W. Pine
- N57°24'E 44.67' to fd. 3/4" iron pipe



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 8/3/2004