

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska _____ (County)	Located In	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S 24 T 25N R 7W	1	
	S 13/24 T 25N R 7W	EW1/64	
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on March 8, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
1 - None EW 1/64 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
1 - W 1/16 Cor. Common to Sec. 13 & 24 - Set 2" Alum. Cap on 5/8" x 34" iron rebar per standard BLM procedure. EW 1/64 - Cor. Common to Sec. 13 & 24 being the NW Cor. of the E 1/2 of NE 1/4 of the NW 1/4 Sec. 24 - Set 2" Alum. Cap on 5/8" x 34" iron rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar - Set blue carsonite post 1' NW
 N5°W 10.52' to set N & T in E. side 6" Forked Cedar
 N77°E 11.90' to set N & T in N. side Tri. 10" Cedar
 South 12.05' to set N & T in E. side 9" R. Maple
 S52°W 14.39' to set N & T in SE side 9" R. Maple EW 1/64 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar
 Set blue carsonite post 1' ENE
 N79°W 26.54' to set N & T in N. side 11" Cedar
 N50°E 7.50' to set N & T in NW side 14" Hemlock
 S56°E 25.18' to set N & T in NE side 8" Cedar
 S26°W 11.69' to set N & T in E. side 7" Cedar

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 8/3/2004