

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 24 T 25N R 7W 12
S 24 T 25N R 7W CESW1/64

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Mar. 10, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
12 - None CESW 1/64 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
12 - CS 1/16 Cor. Sec. 24 - Set 2" Alum. Cap on 5/8" x 34" iron rebar per standard BLM procedure. Centerline of E-W 2-track is 5.5' S. CESW 1/64 - being the SE Cor. of the W 1/2 of NE 1/4 of the SW 1/4, Sec. 24 - Set 2" Alum. Cap on 5/8" x 34" iron rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
12 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar - Set blue carsonite post w/ loc tag 1' SE S18°E 44.83' to set N & T in W. side 8" W. Pine S28°W 31.11' to set N & T in SE side 5" R. Pine N38°W 20.48' to set N & T in E. side 11" J. Pine N34°E 65.75' to set N & T in E. side 8" J. Pine CESW 1/64 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar Set blue carsonite post w/ loc tag 1' SW N6°E 20.43' to set N & T in W. side 20" R. Pine N73°E 9.59' to set N & T in N. side 9" Spruce S3°W 65.47' to set N & T in E. side 16" W. Pine S40°W 38.93' to set N & T in S. side 20" R. Pine

Signed by: Craig W. McVean Date: 8/3/2004
Surveyor's Michigan License No.: 39088